DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
HALIFAX VT 112							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	2.110	F	OM-3R	12	36				1						X											BRIDGE #3			
		F	OM-3R	12	36			3.00								1		9 X								INSTALL BEHIND RAIL WITH 4 FEET OF VERTICAL CLEARANCE TO BOTTOM OF SIGN.	X		
SB	2.080	E	OM-3L	12	36			3.00•					1		X					•THIS SIGN WAS INSTALLED IN LATE 2009. AT FINAL INSPECTION IT WAS MISSING AND HAD TO BE REPLACED.						BRIDGE #3			
		E	OM-3L	12	36			3.00								1		9 X								INSTALL BEHIND RAIL WITH 4 FEET OF VERTICAL CLEARANCE TO BOTTOM OF SIGN.	X		
SB	1.985	F	W1-2L	30	30		CURVE LEFT						1		X														
SB	1.865	F	W1-5L	30	30	FY		6.25								1		15 X								INSTALL 290 FT ± NORTH OF (IN ADVANCE OF) THE "NO PARKING BEGIN" SIGN ASSEMBLY.	X		
SB	1.810	F	R8-3A	24	24								1		X													
		F	VR-644	24	12								1															
		F	R7-201A	12	6								1															
		F	R8-3A	24	24			4.00								1		15 X									X		
		F	VR-644	24	12			2.00																		RED ON WHITE SHEETING		6	
		F	R7-201A	12	6			0.50																			X		
SB	1.760	F	R8-3A	24	24								~~1~~		~~X~~											NO REMOVALS -			
		F	R7-201A	12	6								~~1~~													SIGNS MISSING			
		E	R8-3A	24	24								~~1~~													SIGNS MISSING			
							SHEET TOTALS	21.75 ~~18.75~~ SF	0.00 SF	0 EA	0 EA	0 EA	6 ~~9~~ EA	0 EA	0 EA	4 EA		~~60~~ 48 FT									
							TOWN TOTALS	640.7	0.0	5.0	10.0	10.0	176	0.0	0.0	111		1665.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Halifax-Whitingham VT112**
PROJECT NUMBER: **STPG SIGN(26)**

FILE NAME: **Halifax.xls** PLOT DATE: **6/22/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
HALIFAX SHEET 19 SHEET **26** OF **46**