DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WHITINGHAM VT 112							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.119	A	W3-5	36	36		SPEED REDUCTION 30 MPH			1				X														
NB	1.160	A	VD-062B	72	16						1				X													
		A	VD-062B	72	16						1																	
		A	VD-062B	72	16		BUSINESS SIGN					1				2		15 15.75 X								SALVAGE BOTH SIGNS ONTO NEW POSTS, AT THE SAME LOCATION.			
		A	VD-062B	72	16		BUSINESS SIGN					1																
NB	1.205	A	R2-1	30	36		SPEED LIMIT 30			1				X														
NB	1.230	A	OM-3R	12	36								1		X												BR #14			
		A	OM-3R	12	36			3.00								1		10.25 X								PROVIDE 4 FT OF VERTICAL CLEARANCE TO THE BOTTOM OF THE SIGN. ASSEMBLY BEHIND RAIL.	X		
NB	1.250	B	OM-3L	12	36								1		X											IN THE NB LANE FACING SB TRAFFIC.			
		B	OM-3L	12	36			3.00								1		10.25 X								PROVIDE 4 FT OF VERTICAL CLEARANCE TO THE BOTTOM OF THE SIGN. ASSEMBLY BEHIND RAIL.	X		
NB	1.370	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		13.25 X								BEHIND RAIL	X		
NB	1.375	A	OM-3R	12	36								1		X											BR #15 PROVIDE 4 FT OF VERTICAL CLEARANCE TO THE BOTTOM OF THE SIGN. ASSEMBLY BEHIND RAIL.	X		
		A	OM-3R	12	36			3.00								1		10.5 X										
NB	1.380	B	OM-3L	12	36								1		X											IN THE NB LANE FACING SB TRAFFIC.			
SIGN SUMMARY SHEET							SHEET TOTALS	14.00	0.00	2	2	2	5	0	0	6		~~90~~ 75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	210.8	0.0	33.0	18.0	18.0	47	0.0	0.0	50		750.0										

PROJECT NAME: **Halifax-Whitingham VT112**
PROJECT NUMBER: **STPG SIGN(26)**

FILE NAME: **Whitingham.xls** PLOT DATE: **6/22/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **M. Miller** CHECKED BY: **S. Menard**
WHITINGHAM SHEET 3 SHEET **35** OF **46**