DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
WHITINGHAM VT 112							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	D1-1A	72	12			6.00																				5
		A	D1-1A	72	12			6.00																				5
NB	1.550	A	M3-3	24	12		SOUTH			1				X														
		A	M1-5	30	24		VERMONT 100			1																		
		A	VM-013	21	15		<--- LEFT (ACUTE)			1																		
		A	M3-1	24	12		NORTH			1																		
		A	M1-5	30	24		VERMONT 100			1																		
		A	M6-2	21	15		RIGHT ---> (45 DEG)			1																		
NB	1.586	A	R1-1	30	30								1		X													
		A	R1-1	30	30			6.25								1		~~15~~ 13.25 X								BEHIND RAIL	X	
SB	1.600	F	M3-3S	24	12								1	X														
		F	M1-5	30	24								1															
		F	M6-2	21	15								1															
		F	M4-5	24	12								1															
		F	M1-5	24	24								1															
							SHEET TOTALS	18.25	0.00	6	0	0	6	0	0	1		~~15~~ 13.25										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	210.8	0.0	33.0	18.0	18.0	47	0.0	0.0	50		750.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Halifax-Whitingham VT112
PROJECT NUMBER: STPG SIGN(26)

FILE NAME: Whitingham.xls
PROJECT MANAGER: N. Avery
DESIGNED BY: M. Miller
WHITINGHAM SHEET 5

PLOT DATE: 6/22/2009
DRAWN BY: I. Shea
CHECKED BY: S. Menard
SHEET 37 OF 46