DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WHITINGHAM VT 112							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	M1-5A	24	24		ROUTE 8A			1																		
		F	M6-2	21	15		RIGHT ---> (45 DEG)			1																		
SB	0.057	E	W1-6	48	24		LARGE ARROW RIGHT			1				X												INSTALLED FACING SB AT NW CORNER OF JCT w/ 8A			
SB	0.057	H	R1-1	30	30								1		X											STATE NUMBERED TOWN HIGHWAY 8A			
		H	R1-1	30	30			6.25								1		12.75 X								THIS IS THE LEFT-SIDE STOP SIGN FOR 8A AT THE JCT w/ VERMONT 112.	X		
SB	0.057	G	VR-017	24	24								1		X											STATE NUMBERED TOWN HIGHWAY 8A INSTALL EAST OF STOP SIGN 100 FT ± SO AS NOT TO OBSCURE VISIBILITY TO STOP SIGN.			
		G	VR-017	24	30			5.00								1		13.25 X										E-141
SB	0.050	H	R1-1	30	30		STOP			1				X												THIS IS THE RIGHT-SIDE STOP SIGN FOR ROUTE 8A.			
SB	0.040	F	W1-6	48	24								1		X													
		F	W1-6	48	24			8.00								2		13 13 X								BEHIND RAIL	X		
SB	0.015	F	OM-3R	12	36			3.00								1		10.5 X								INSTALL AT NORTHERLY ABUTMENT, BEHIND RAIL. PROVIDE 4 FT CLEARANCE.	X		
SB	0.018	F	M3-3S	24	12		SOUTH			1				X														
SB	0.018	F	M1-5	30	24		VERMONT 112			1																		
SB	0.000	G	VD-024	60	7.5		HALIFAX I WHITINGHAM			1				X														
		G	VD-700	6	10		1120-1308-0585			1																		
SIGN SUMMARY SHEET							SHEET TOTALS	22.25 SF	0.00 SF	8 EA	0 EA	0 EA	3 EA	0 EA	0 EA	5 EA		~~75~~ 62.5 FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	210.8	0.0	33.0	18.0	18.0	47	0.0	0.0	50		750.0										

PROJECT NAME: **Halifax-Whitingham VT112**
PROJECT NUMBER: **STPG SIGN(26)**

FILE NAME: **Whitingham.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
WHITINGHAM SHEET 10

PLOT DATE: **6/22/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **S. Menard**
SHEET **42** OF **46**