

# COMPOSITE QUANTITY SHEET

					GROTON - RYEGATE STP SURF (16)				BARRE TOWN - ORANGE STP SURF (15)					QUANTITIES		DESCRIPTIONS			
					ALT A	ALT B	ROADWAY	FULL C.E.	ALT A	ALT B	BRIDGE	ROADWAY	FULL C.E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	
																BEGIN ITEMS COMMON TO ALL ALTERNATES			
							5,680				19,000		24,680	LF	SHOULDER BERM REMOVAL	203.40	EST.		
							1				1		2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.		
							600				2,600		3,200	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	35		
							250				1,750		2,000	TON	AGGREGATE SHOULDERS	402.12	22		
							20				75		95	CWT	EMULSIFIED ASPHALT	404.65	-		
							1				1		2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-		
							2,500				25,000		27,500	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	EST.		
											240		240	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	6		
											100		100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL W/COARSE AGGREGATE	580.20	EST.		
							85				500		585	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.		
							500				1,500		2,000	HR	FLAGGERS	630.15	EST.		
								0.5				0.5	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-		
							0.5				0.5		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-		
											1		1	LS	TRAFFIC CONTROL (STP SURF (15))	641.10	-		
											1		1	LS	TRAFFIC CONTROL (STP SURF (16))	641.10	-		
							46,900				198,000		244,900	LF	4 INCH WHITE LINE	646.20	-		
							46,900				198,000		244,900	LF	4 INCH YELLOW LINE	646.21	-		
											24		24	EA	LETTER OR SYMBOL	646.30	-		
							600				2,500		3,100	EA	LINE STRIPING TARGETS	646.76	EST.		
							8,000				32,000		40,000	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.		
							1				1		2	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-		
							1				1		2	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-		
							150				650		800	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680			
							5				20		25	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.		
															END ITEMS COMMON TO ALL ALTERNATES				
															BEGIN ALTERNATE A				
					52,150				170,500				222,650	SY	** SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	105		
															END ALTERNATE A				
															BEGIN ALTERNATE B				
						1			1				2	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-		
						3,100			10,000				13,100	TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR LATEX)	900.680	117		
						350			1,200				1,550	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	16.4		
															END ALTERNATE B				
															PROJECT NAME: BARRE TOWN - ORANGE/GROTON - RYEGATE				
															PROJECT NUMBER: STP SURF(15)/STP SURF(16)				
															FILE NAME: p09b038.dgn		PLOT DATE: 10-NOV-2011		
															PROJECT LEADER: MARSHIA		DRAWN BY: LOCKE		
															DESIGNED BY: LOCKE		CHECKED BY: PAVT MGMT		
															IPARM FILE: p09b038cqs01.i		SHEET 5 OF 24		
															** REVISED 01-29-10 BY KML				
															CHANGED (PAVER PLACED SURFACE TREATMENT, TYPE B) TO				
															(PAVER PLACED SURFACE TREATMENT, TYPE C)				