QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			ALT A	ALT B	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
									BEGIN ITEMS COMMON TO ALL ALTERNATES		
					5,680		5,680	LF	SHOULDER BERM REMOVAL	203.40	EST.
					1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
					600		600	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	6
					250		250	TON	AGGREGATE SHOULDERS	402.12	22
					20		20	CWT	EMULSIFIED ASPHALT	404.65	-
					1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
					2,500		2,500	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD	417.20	EST.
					85		85	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
					500		500	HR	FLAGGERS	630.15	EST.
						0.5	0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
					0.5		0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
					1		1	LS	TRAFFIC CONTROL (STP SURF(16))	641.10	-
					46,900		46,900	LF	4 INCH WHITE LINE	646.20	-
					46,900		46,900	LF	4 INCH YELLOW LINE	646.21	-
					600		600	EA	LINE STRIPING TARGETS	646.76	EST.
			8,000				8,000	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.
					1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
					1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-
					150		150	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	-
					5		5	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
									END ITEMS COMMON TO ALL ALTERNATES		
									BEGIN ALTERNATE A		
			52,150				52,150	SY	•• SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	30
									END ALTERNATE A		
									BEGIN ALTERNATE B		
				1			1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
				3,100			3,100	TON	SPECIAL PROVISION (6.3 MM POLYMER - MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR LATEX)	900.680	60
				350			350	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	4
									END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BIT. PAVEMENT
222	SY	BEGIN PROJECT
222	SY	END PROJECT
150	SY	DRIVES AND TOWN HIGHWAYS
6	SY	ROUNDING
600	SY	TOTAL
		ALTERNATE A
		SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C) ••
52,120	SY	MAINLINE
30	SY	ROUNDING
52,150	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER - MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR LATEX)
3,040	TON	MAINLINE
60	TON	ROUNDING
3,100	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

•• REVISED 01-29-10 BY KML
CHANGED (PAVER PLACED SURFACE TREATMENT, TYPE B) TO (PAVER PLACED SURFACE TREATMENT, TYPE C)

PROJECT NAME: GROTON - RYEGATE
PROJECT NUMBER: STP SURF(16)

FILE NAME: p09b038.dgn
PROJECT LEADER: MARSHIA
DESIGNED BY: LOCKE
p09b040qs.i

PLOT DATE: 10-NOV-2011
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 19 OF 24