QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ALT. A	ALT. B	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ITEMS COMMON TO ALL ALTERNATES		
			20,500		20,500	LF	SHOULDER BERM REMOVAL	203.40	394
			1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
			1050		1050	TON	AGGREGATE SHOULDERS	402.12	50
			1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		180			180	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	EST.
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.
			1,000		1,000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	-
			2,000		2,000	HR	FLAGGERS	630.15	EST.
				1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1		1	LS	TRAFFIC CONTROL	641.10	-
			4		4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			149 000		149 000	LF	4 INCH WHITE LINE	646.20	676 △
			149 000		149 000	LF	4 INCH YELLOW LINE	646.21	676 △
			25		25	LF	24 INCH STOP BAR	646.26	-
			8		8	EA	LETTER OR SYMBOL	646.30	-
			3 000		3 000	EA	LINE STRIPING TARGETS	646.76	EST
							END ITEMS COMMON TO ALL ALTERNATES		
							BEGIN ALTERNATE A (COLD PLANE AND PAVE)		
164 000					164 000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	437
15 000					15 000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	688
1					1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
1					1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
1					1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
150					150	HR	POWER BROOM RENTAL, TYPE 1	608.30	EST.
75 000					75 000	LF	TEMPORARY 4 INCH WHITE LINE	646.600	816
75 000					75 000	LF	TEMPORARY 4 INCH YELLOW LINE	646.610	816
25					25	LF	TEMPORARY 24'' STOP BAR	646.680	-
17					17	EA	TEMPORARY LETTER OR SYMBOL	646.690	-
			1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
1100					1100	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	10
							END ALTERNATE A (COLD PLANE AND PAVE)		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		COLD PLANING, BITUMINOUS CONCRETE PAVEMENT
163 563	SY	MAINLINE
437	SY	ROUNDING
164 000	SY	TOTAL
		SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)
1090	CWT	MAINLINE
10	CWT	ROUNDING
1100	CWT	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
14 312	TON	MAINLINE
688	TON	ROUNDING
15 000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

ALTERNATE A—COLD PLANE AND PAVE

△ REVISED 5/3/2010

PROJECT NAME: RYEGATE - NEWBURY
PROJECT NUMBER: IM SURF (17)

FILE NAME: 09B042\p09B042.dgn
PROGRAM MANAGER : K. MARSHIA
DESIGNED BY: JLR
IPARM FILE NAME: p09B042_06.i

PLOT DATE: 01-AUG-2011 15:13
DRAWN BY: JLR
CHECKED BY: PAVT MGMT
SHEET 6 OF 10