QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ALT. A	ALT. B	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN ALTERNATE B (HOT IN-PLACE RECYCLE)		
	1				1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
	100				100	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
	149 000				149 000	LF	TEMPORARY 4 INCH WHITE LINE	646.600	676
	149 000				149 000	LF	TEMPORARY 4 INCH YELLOW LINE	646.610	676
	50				50	LF	TEMPORARY 24'' STOP BAR	646.680	-
	34				34	EA	TEMPORARY LETTER OR SYMBOL	646.690	-
	164 000				164 000	SY	SPECIAL PROVISION (HOT IN PLACE RECYCLE)	900.675	437
	2 700				2 700	TON	SPECIAL PROVISION (MICRO-SURFACE TREATMENT , TYPE II)	900.680	76
	2 100				2 100	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	56
							END ALTERNATE B (HOT IN-PLACE RECYCLE)		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE B
		HOT IN-PLACE RECYCLE
163 563	SY	MAINLINE
437	SY	ROUNDING
164 000	SY	TOTAL
		MICRO-SURFACE TREATMENT, TYPE II
2 624	TON	MAINLINE
76	TON	ROUNDING
2 700	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

ALTERNATE B—HOT IN-PLACE RECYCLE
REVISED 5/3/2010

PROJECT NAME: RYEGATE - NEWBURY
PROJECT NUMBER: STP SURF (17)

FILE NAME: 09B042\p09B042.dgn
PROJECT LEADER: K. MARSHIA
DESIGNED BY: JLR
IPARM FILE NAME: p09B042_7.i

PLOT DATE: 22-OCT-2012 13:10
DRAWN BY: JLR
CHECKED BY: PAVT MGMT
SHEET 7 OF 10