DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
LUDLOW VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.455	A	VW-619	30	30		SHOULDER NARROWS						1		X														
NB	1.558	A	W1-10L	30	30		CURVE LEFT w/ INTERSECTING SIDE ROADS BOTH SIDES						1		X														
NB	1.612	A	W2-1Mh	30	30			6.25								1		X									INSTALL BEHIND RAIL 225 FT± SOUTH OF THE "ST. JOSEPH'S" BUSINESS SIGN (NEXT ENTRY)		6	
NB	1.655	A	VD-062B	72	16		BUSINESS SIGN			1				X															
NB	1.710	C	VR-017	24	24								1		X													ANDOVER RD (TH-1); SOUTHERLY APPROACH			
		C	VR-017	24	30			5.00								1		X									INSTALL AT A POINT JUST BEYOND THE CONVERGANCE OF THE TWO APPROACHES			E-141
NB	1.718	D	R1-1	24	24								1		X													ANDOVER RD (TH-1); SOUTHERLY APPROACH			
		D	R1-1	30	30			6.25								1		X										X		
NB	1.754	D	R1-1	24	24								1		X													ANDOVER RD (TH-1) NORTHERLY APPROACH			
		D	R1-1	30	30			6.25								1		X										X		
NB	1.773	A	M3-1	24	12			2.00								1		X									GREEN ON WHITE SHEETING	X		
		A	M1-5	30	24			5.00																			INSTALL 100 FT± NORTH OF THE NORTHERLY APPROACH TO ANDOVER RD (TH-1)			E-136B
NB	1.837	A	VD-123	36	36		511 TRAVEL INFO			1				X															
NB	2.126	C	VR-017	24	24								1		X													EVERGREEN ACRES RD (TH-71)			
		C	VR-017	24	30			5.00								1		X												E-141
							SHEET TOTALS	35.75	0.00	2	0	0	6	0	0	6		90										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	647.4	0.0	13.0	4.0	4.0	135	0.0	0.0	106		1590.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Ludlow.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
LUDLOW SHEET 2

PLOT DATE: **9/4/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **N. Avery**
SHEET **10** OF **204**