DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
LUDLOW VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W1-2L	30	30			6.25								1		X									X		
SB	8.230	F	R2-1	24	30								1		X														
		F	R2-1	24	30			5.00								1		X								(ACROSS FROM THE NB SPEED LIMIT 35 SIGN)	X		
SB	8.064	F	n/a	n/a	n/a		REMOVE EMPTY POST								X											REMOVE EMPTY POST			
SB	7.930	F	VW-054L	30	30			6.25								1		X								INSTALL 185 FT± NORTH OF THE EXISTING SIGN, WHICH WILL BE REMOVED			E-154
SB	7.895	F	VW-133A	30	30		HIDDEN DRIVE LEFT						1		X														
SB	7.705	F	W1-4R	30	30		REVERSE CURVE RIGHT						1		X														
		F	W13-1	18	18		35 MPH (PLAQUE)						1																
SB	7.655	F	W1-4R	30	30			6.25								1		X								INSTALL 265 FT± SOUTH OF PREVIOUS POSITION	X		
SB	7.530	F	VW-133A	30	30		HIDDEN DRIVE LEFT						1		X														
SB	7.455	F	VW-054L	30	30			6.25								1		X								INSTALL 400 FT± SOUTH OF PREVIOUS POSITION; MAINTAIN 10 FT MIN TO POLE			E-154
SB	7.255	F	W1-2L	30	30		CURVE LEFT						1		X														
SB	7.220	F	VW-219	30	30		SUMMER CAMP AREA						1		X														
		F	W1-2L	30	30			6.25								1		X										X		
SB	7.105	F	R2-1	24	30		SPEED LIMIT 45						1		X														
							SHEET TOTALS	36.25 SF	0.00 SF	0 EA	0 EA	0 EA	8 EA	0 EA	0 EA	6 EA	90 FT												
							TOWN TOTALS	647.4	0.0	13.0	4.0	4.0	135	0.0	0.0	106	1590.0												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Ludlow.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
LUDLOW SHEET 15

PLOT DATE: **9/4/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **N. Avery**
SHEET **23** OF **204**