DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
PLYMOUTH VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	5.998	C	VR-017	24	30								1		X											RICKS RD (TH-12)			
		C	VR-017	24	30			5.00								1		X											E-141
NB	6.004	D	R1-1	30	30								1		X											RICKS RD (TH-12)			
		D	R1-1	30	30			6.25								1		X								REINSTALL THE STREET NAME SIGN ON TOP OF THE NEW STOP SIGN POST	X		
NB	6.016	A	R2-1	24	30			5.00								1		X								INSTALL 65 FT± NORTH OF RICKS RD (TH-12)	X		
NB	6.128	A	W1-5L	30	30		WINDING CURVES LEFT (SYMBOL)						1		X														
NB	6.250	A	W1-5L	30	30			6.25								1		X								INSTALL 645 FT± NORTH OF PREVIOUS POSITION, BEHIND RAIL.	X		
		A	W7-3A	24	18			3.00																			X		
NB	6.796	A	W11-6	30	30								1		X											BEHIND RAIL			
		A	W11-6	30	30			6.25								1		X								HINGED SIGN; **INSTALL IN CLOSED POSITION**			E-153
NB	7.062	A	W1-5L	30	30		WINDING CURVES LEFT						1		X											BEHIND RAIL			
NB	7.297	A	W1-2Mb L	30	30			6.25								1		X								INSTALL 265 FT± SOUTH OF THE "WATCH FOR TURNING VEHICLES" SIGN		6	
NB	7.363	A	VW-205	30	30		WATCH FOR TURNING VEHICLES						1		X														
NB	7.520	A	VW-285	30	30								1		X											REMOVE ATTACHED FLAGS			
		A	VW-285	30	30			6.25								1		X										6	
							SHEET TOTALS	44.25	0.00	0	0	0	7	0	0	7		105											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	668.4	0.0	31.0	4.0	4.0	135	0.0	0.0	111		1665.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT110**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Plymouth.xls** PLOT DATE: **9/8/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **M. Miller** CHECKED BY: **N. Avery**
PLYMOUTH SHEET 9 SHEET **36** OF **204**