DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
PLYMOUTH VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	M1-5	24	24			5.00																					E-136B
SB	0.107	F	R2-1	24	30								1		X											BEHIND RAIL			
		F	R2-1	24	30			5.00								1		X									X		
SB	0.033	G	VR-017	24	30								1		X											LIBRARY RD (TH-35)			
		G	VR-017	24	30			5.00								1		X											E-141
SB	0.027	H	R1-1	30	30								1		X											LIBRARY RD (TH-35)			
		H	R1-1	30	30			6.25								1		X									X		
							SHEET TOTALS	21.25	0.00	0	0	0	3	0	0	3		45											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	668.4	0.0	31.0	4.0	4.0	135	0.0	0.0	111		1665.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT110**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Plymouth.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
PLYMOUTH SHEET 21

PLOT DATE: **9/8/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **N. Avery**