DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRIDGEWATER VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	D2-1	72	12			6.00																			5	
SB	0.862	F	W11-1	30	30								1		X													
		F	W16-1	18	24								1															
		F	W11-1	30	30		SHARE THE ROAD	6.25								1		X									X	
		F	W16-1	18	24		SPEED LIMIT 50	3.00																			X	
SB	0.824	F	R2-1	24	30			5.00								1		X								INSTALL 200 FT± SOUTH OF BIKE / SHARE THE ROAD SIGNS	X	
SB	0.045	F	W1-2R	30	30			6.25								1		X								INSTALL 240 FT± NORTH OF AND ACROSS FROM THE BRIDGEWATER / PLYMOUTH TOWN LINE SIGN.	X	
							VT 100 BECOMES US 4. RESUME VT 100 IN KILLINGTON																					
							SHEET TOTALS	26.50	0.00	0	0	0	2	0	0	3		45										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	111.1	0.0	12.0	1.0	1.0	25	0.0	0.0	15		225.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Bridgewater.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **M. Miller**
BRIDGEWATER SHEET 5

PLOT DATE: **9/15/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **N. Avery**