DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
KILLINGTON			**VT 100**				FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W13-1	18	18								1														
		F	W1-5L	30	30			6.25								1		X									X	
		F	W13-1	18	18			2.25																			X	
SB	1.132	F	W1-4L	30	30			6.25								1		X								INSTALL 200 FEET NORTH OF BUSINESS SIGNS	X	
		F	W13-1	18	18			2.25																			X	
SB	1.170	F	VD-062BRN	72	16		BUSINESS SIGN			1				X														
		F	VD-062B	72	16		BUSINESS SIGN			1				X														
SB	1.085	F	W1-10R	30	30								1		X													
		F	S3-1	30	30								1													RESET TO SPEC, NEW POSTS 17.33+17.50+0.42 LENGTHEN POST TO MEET SPEC +0.42		
		F	W1-10R	30	30			6.25								2		X								INSTALL ABOVE SCHOOL BUS STOP AHEAD SIGN	X	
		F	S3-1	30	30			6.25																			X	
SB	1.000	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X													
SB	0.955	F	VW-054R	30	30			6.25								1		X								INSTALL ACROSS FROM LAKEWOOD DRIVE (TH-60)		E-154
SB	0.830	F	VW-205	36	36								1		X													
		F	VW-205	36	36			9.00								2		X										E-154
							SHEET TOTALS	44.75	0.00	2	0	0	5	0	0	7		105										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	567.0	0.0	28.0	0.0	0.0	114	0.0	0.0	88		1320.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Killington.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
KILLINGTON SHEET 11

PLOT DATE: **9/8/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **N. Avery**
SHEET **64** OF **204**