DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
PITTSFIELD VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	3.780	A	R2-1	24	30		SPEED LIMIT 35 / LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X											
NB	3.790	C	VR-017	24	30			5.00								1		X									TH-7, VILLAGE GREEN (SOUTH) INSTALL 20 FEET FROM VT-100			E-141
NB	3.790	D	R1-1	30	30		STOP						1		X												TH-7, VILLAGE GREEN (SOUTH) SIGN AND POST ARE IN ISLAND			
		D	R1-1	30	30			6.25								1		X										X		
NB	3.790	A	R2-1	24	30		SPEED LIMIT 35			REMOVED: CONFLICT WITH NEW ~~1~~ 1				X																
NB	3.800	D	R1-1	30	30		STOP						1		X												TH-7, VILLAGE GREEN (SOUTH)			
		D	R1-1	30	30			6.25								1		X									REINSTALL STREET SIGN ABOVE NEW SIGN.	X		
NB	3.900	A	W1-2R	30	30								1		X															
		A	W1-2R	30	30		LEGAL LOAD LIMIT 24,000 POUNDS	6.25								1		X											X		
NB	3.929	C	VR-017	24	30			5.00								1		X									INSTALL 20 FEET FROM VT-100			E-141
NB	3.930	D	R1-1	30	30		STOP						1		X												TH-7, VILLAGE GREEN (NORTH)			
		D	R1-1	30	30			6.25								1		X									ON ISLAND	X		
NB	3.932	D	R1-1	30	30		STOP						1		X												TH-7, VILLAGE GREEN (NORTH)			
		D	R1-1	30	30			6.25								1		X										X		
NB	4.090	A	R2-1	24	30		SPEED LIMIT 40			1				X																
							SHEET TOTALS	46.25 SF	0.00 SF	~~2~~ 1 EA	0 EA	0 EA	~~5~~ 6 EA	0 EA	0 EA	8 EA		120 FT										
							TOWN TOTALS	297.1	0.0	15.0	1.0	1.0	51	0.0	0.0	52		780.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Pittsfield.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
PITTSFIELD SHEET 4

PLOT DATE: **9/9/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **N. Avery**
SHEET **75** OF **204**