DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STOCKBRIDGE VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	W7-3A	24	18			3.00																			X		
NB	0.924	C	VR-017	24	30								1		X											CANTON DR (TH-49)			
		C	VR-017	24	30			5.00								1		X								RE-INSTALL STREET SIGN BACK ONTO THE TOP OF THIS NEW POST			E-141
NB	0.932	D	R1-1	30	30								1		X											CANTON DR (TH-49)			
		D	R1-1	30	30			6.25								1		X								REINSTALL STREET NAME SIGN ON TOP OF NEW POST	X		
NB	1.340	A	VD-062B	72	16						1				X											ONLY ONE SIGN EXISTING			
		A	VD-062B	72	16						~~1~~																		
		A	VD-062B	72	16		BUSINESS SIGN					1				2		X								SALVAGE THE SIGNS ONTO NEW POSTS; "OLD HOTEL" ON TOP			
		A	VD-062B	72	16		BUSINESS SIGN					~~1~~														ONLY ONE SIGN			
NB	1.570	C	VR-017	24	30								1		X											SOUTH HILL RD (TH-19)			
		C	VR-017	24	30			5.00								1		X											E-141
NB	1.578	D	R1-1	30	30								1		X											SOUTH HILL RD (TH-19)			
		D	R1-1	30	30			6.25								1		X								RE-INSTALL STREET SIGN BACK ONTO THE TOP OF THIS NEW POST	X		
NB	1.635	A	W2-5	30	30								1		X														
		A	W16-2	24	18								1																
SIGN SUMMARY SHEET							SHEET TOTALS	25.50	0.00	0	~~1~~ 2	~~1~~ 2	6	0	0	6			90									
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT									
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	676.7	0.0	3.0	8.0	8.0	140	0.0	0.0	107			1605.0									

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Stockbridge.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **M. Miller**
STOCKBRIDGE SHEET 2

PLOT DATE: **9/9/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **N. Avery**
SHEET **81** OF **204**