DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
HANCOCK VT-100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	0.357	F	R2-1	24	30								1		X														
		F	R2-1	24	30			5.00								1		X									X		
SB	0.323	F	VW-544	30	30		EMERGENCY VEHICLES						1		X														
SB	0.288	F	VW-081L	30	30		TRUCKS ENTERING						1		X														
		F	VW-544	30	30			6.25								1		X											E-154
SIGN SUMMARY SHEET							SHEET TOTALS	11.25	0.00	0	0	0	3	0	0	2	30												
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT												
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	370.6	0.0	32.0	6.0	6.0	78	0.0	0.0	50	750.0												

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Hancock.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **J. Kelly**
HANCOCK SHEET 14

PLOT DATE: **9/10/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **J. Kelly**
SHEET **135** OF **204**