| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WARREN** | | **VT 100** | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| NB | 5.796 | A | S3-1 | 30 | 30 | | SCHOOL BUS STOP AHEAD | | | | | | 1 | | X | | | | | | | | | | | | | |
| NB | 5.830 | A | S3-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL 150' +/- NORTH OF ORIGINAL SIGN LOCATION | X | | |
| NB | 5.840 | A | W11-1 | 30 | 30 | | BICYCLE | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | A | W16-1 | 18 | 18 | | SHARE THE ROAD | | | | | | 1 | | | | | | | | | | | | | | | |
| NB | 5.860 | A | W11-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL 50' +/- NORTH OF ORIGINAL SIGN LOCATION | X | | |
| | | A | W16-1 | 18 | 18 | | | 3.00 | | | | | | | | | | | | | | | | | | | X | |
| NB | 5.882 | A | VD-062AL | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | |
| NB | 5.894 | A | OM-3R | 12 | 36 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | A | OM-3R | 12 | 36 | | | 3.00 | | | | | | | | 1 | | X | | | | | | | | | X | |
| NB | 5.920 | B | OM-3L | 12 | 36 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | B | OM-3L | 12 | 36 | | | 3.00 | | | | | | | | 1 | | X | | | | | | | | | X | |
| NB | 5.940 | C | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | VOLKSTOWN RD TH-41 | | | |
| | | C | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | RESET TO SPEC, NEW POST. | | | E-141 |
| NB | 5.940 | D | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | VOLKSTOWN RD TH-41 | | | |
| | | D | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | | X | |
| | | | | | | | SHEET TOTALS | 32.75 | 0.00 | 1 | 0 | 0 | 7 | 0 | 0 | 6 | | 90 | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 465.2 | 0.0 | 65.0 | 10.0 | 10.0 | 97 | 0.0 | 0.0 | 90 | | 1350.0 | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Ludlow-Waitsfield VT100**
PROJECT NUMBER: **STPG SIGN(27)**

FILE NAME: **Warren.xls**
PROJECT MANAGER: **N. Avery**
DESIGNED BY: **D. Crossley**
WARREN SHEET 8

PLOT DATE: **9/14/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **J. Kelly**