DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT)	2.00 (LB / FT)	2.50 (LB / FT)	FOUNDATION	3.00 (LB / FT)	3.50 (LB / FT)	4.00 (LB / FT)	5.00 (LB / FT)			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
MORETOWN VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.220	A	R10-7	24	30		DO NOT BLOCK INTERSECTION			1				X															
NB	1.223	C	VR-017	24	30		LEGAL LOAD LIMIT 24000			1				X												COBB HILL RD TH 6			
NB	1.231	D	R1-1	30	30		STOP			1				X												COBB HILL RD TH 6			
NB	1.208	A	M3-4	24	12		WEST			1				X															
		A	M1-4	24	24		US2			1																			
		A	M3-1S	24	12		NORTH			1																			
		A	M1-5	30	24		VERMONT 100			1																			
		A	M6-1S	21	15		LEFT			1																			
		A	M3-2	24	12		EAST			1																			
		A	M1-4	24	24		US 2			1																			
		A	M6-1	21	15		RIGHT			1																			
		A	M4-5I	24	12		TO			1																			
		A	M1-1	24	24		I-89			1																			
		A	M6-1I	21	15		LEFT			1																			
SIGN SUMMARY SHEET							SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0	0												
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT												
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	228.6	0.0	22.0	0.0	0.0	60	0.0	0.0	27	405.0												

PROJECT NAME: **Mortown-Newport Town VT100**
PROJECT NUMBER: **STPG SIGN(28)**

FILE NAME: **Moretown.xls** PLOT DATE: **9/16/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **D. Crossley** CHECKED BY: **J. Kelly**
MORETOWN SHEET 6 SHEET **14** OF **166**