DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
DUXBURY VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	S4-4	24	10		WHEN FLASHING			1																		
		A	R2-1	24	30		SPEED LIMIT 35			1																		
NB	5.610	A	D1-1E	72	10								1		X													
		A	D1-2 R	72	20		CROSSETT BROOK MIDDLE SCHOOL →	10.00								2		X									5	
NB	5.670	D	R1-1	30	30		STOP			1				X														
NB	5.719	A	R2-1	24	30		SPEED LIMIT 40						1		X													
		A	R2-1	24	30			5.00								1		X									X	
NB	5.760	A	W1-4L	30	30		LEFT REVERSE CURVE						1		X													
NB	5.820	A	W1-4L	30	30			6.25								1		X									INSTALL 300'+/- NORTH OF ORIGINAL SIGN LOCATION	X	
NB	5.871	A	W1-8	18	24								1		X													
		A	W1-8	18	24			3.00								1		X									X	
NB	5.896	A	W1-8	18	24								1		X													
		A	W1-8	18	24			3.00								1		X									X	
NB	5.916	A	W1-8	18	24								1		X													
		A	W1-8	18	24			3.00								1		X									X	
SIGN SUMMARY SHEET							SHEET TOTALS	30.25	0.00	3	0	0	6	0	0	7		105									
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT									
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	345.2	0.0	68.0	1.0	1.0	65	0.0	0.0	62		930.0									

PROJECT NAME: **Moretown-Newport Town VT100**
PROJECT NUMBER: **STPG SIGN(28)**
FILE NAME: **Duxburv.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **D. Crossley**
DUXBURY SHEET 5
PLOT DATE: **9/16/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **J. Kelly**
SHEET **23** OF **166**