DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75	2.00	2.50	TUBULAR STEEL Ø (IN) FOUNDATION	(LB / FT) 3.00	3.50	4.00	5.00	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
WATERBURY VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	0.790	A	VR-921	30	30								1		X														
		A	VR-921	30	30			6.25								1		X										E-145A
NB	0.820	C	R4-7	24	30		RIGHT BULL NOSE			1				X														
		C	OM1-1	18	18		YELLOW CLUSTER			1																		
NB	0.900	A	VD-062B	72	16		BUSINESS SIGN			1				X														
		A	VD-062AS	72	16		BUSINESS SIGN			1																		
NB	0.930	A	S3-1	30	30		SCHOOL BUS STOP AHEAD			1				X														
NB	0.980	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		X									X	
NB	1.022	C	VR-017	24	24								1		X												MILL ST TH-20		
		C	VR-017	24	30			5.00								1		X										E-141
NB	1.028	D	R1-1	24	24								1		X												MILL ST TH-20		
		D	R1-1	30	30			6.25								1		X									X	
NB	1.128	C	VR-017	24	24								1		X												LAUREL LN TH-21		
		C	VR-017	24	30			5.00								1		X										E-141
							SHEET TOTALS	27.50	0.00	5	0	0	5	0	0	5		75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN TOTALS	622.8	0.0	89.0	5.0	5.0	115	2.0	0.0	105		1575.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Moretown-Newport Town VT100**
PROJECT NUMBER: **STPG SIGN(28)**

FILE NAME: **Waterburv.xls** PLOT DATE: **9/17/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **D. Crossley** CHECKED BY: **N. Avery**
WATERBURY SHEET 3 SHEET **35** OF **166**