DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STOWE VT 100							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.532	B	W1-6	48	24		RIGHT ===> LARGE ARROW			1				X														
NB	1.544	C	VR-017	24	30								1		X											GOLD BROOK RD TH-7			
		C	VR-017	24	30			5.00								1		X											E-141
NB	1.552	D	R1-1	24	24								1		X											GOLD BROOK RD TH-7			
		D	R1-1	30	30			6.25								1		X									X		
NB	1.646	A	W1-2R	30	30		RIGHT CURVE			1				X															
NB	1.794	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		X									X		
NB	1.933	A	W11-1	30	30		BICYCLE SYMBOL			1				X															
		A	W16-1	18	24		SHARE THE ROAD			1																			
NB	1.989	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		X									X		
NB	2.067	A	W11-6	30	30								1		X														
		A	W11-6	30	30			6.25								1		X									X		
NB	2.117	A	W3-5	36	36		SPEED REDUCTION SPEED LIMIT 30			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	27.50	0.00	5	0	0	5	0	0	5		75									
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT									
VERMONT AGENCY OF TRANSPORTATION							TOWN TOTALS	582.8	0.0	65.0	6.0	6.0	105	0.0	0.0	103		1545.0									

PROJECT NAME: **Moretown-Newport Town VT100**
PROJECT NUMBER: **STPG SIGN(28)**
FILE NAME: **Stowe.xls** PLOT DATE: **9/29/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **D. Crossley** CHECKED BY: **N. Avery**
STOWE SHEET 4 SHEET **59** OF **166**