| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS | | EXISTING SIGNS | | | | EXIST POST | | NUMBER OF NEW POSTS | SQUARE STEEL (IN) | | | TUBULAR STEEL Ø (IN) | | | | | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | "A" | "B" | RETAIN | SALVAGE FROM | SALVAGE TO | REMOVE | RETAIN | REMOVE | | 1.75 | 2.00 | 2.50 | FOUNDATION | 3.00 | 3.50 | 4.00 | 5.00 | | | DETAIL IN SHS | DETAIL ON SHEET NUMBER | DETAIL ON STD SHEET NUMBER |
| | | | | | | | | | | | | | | | | | (LB / FT) | | | | (LB / FT) | | | | | | | | |
| | | | | | | | | | | | | | | | | | 1.88 | 2.42 | 3.35 | | 7.60 | 9.00 | 10.80 | 14.60 | | | | | |
| **MORRISTOWN VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| NB | 6.170 | A | VD-062B | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | VD-062AS | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | VD-062AL | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | | | | | | | | | | | | | | | | |
| NB | 6.188 | A | VR-039 | 24 | 18 | | STATE HIGHWAY BEGINS | | | | 1 | 1 | | | | 1 | | X | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | SPEED LIMIT 40 | | | | 1 | 1 | | | | | | | | | | | | | | | | | |
| NB | 6.302 | A | VR-932 | 48 | 30 | | LEFT "ONLY"/THRU/RIGHT "ONLY" | | | 1 | | | | X | | | | | | | | | | | | | | | |
| NB | 6.376 | C | VR-017 | 24 | 30 | | LEGAL LOAD LIMIT 24,000 LBS | | | 1 | | | | X | | | | | | | | | | | | NORTHGATE AVE. TH-101 | | | |
| NB | 6.384 | D | R1-1 | 30 | 30 | | STOP | | | 1 | | | | X | | | | | | | | | | | | NORTHGATE AVE. TH-101 | | | |
| NB | 6.465 | A | M2-1S | 21 | 15 | | JCT | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | VERMONT 15 | | | 1 | | | | | | | | | | | | | | | | | | | |
| NB | 6.495 | A | VR-921MR | 30 | 30 | | THRU/MODIFIED RIGHT "ONLY" | | | 1 | | | | X | | | | | | | | | | | | | | | |
| NB | 6.532 | A | D1-1A | 72 | 12 | | <--- JOHNSON 7 | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 12 | | <--- JEFFERSONVILLE 16 | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 12 | | WOLCOTT 8 ---> | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 12 | | HARDWICK 13 ---> | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 0.00 | 0.00 | 13 | 2 | 2 | 0 | 0 | 0 | 1 | 15 | | | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 369.7 | 0.0 | 77.0 | 5.0 | 5.0 | 65 | 0.0 | 0.0 | 68 | 1020.0 | | | | | | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Moretown-Newport Town VT100**
PROJECT NUMBER: **STPG SIGN(28)**

FILE NAME: **Morristown.xls** PLOT DATE: **9/29/2009**
PROJECT MANAGER: **N. Avery** DRAWN BY: **I. Shea**
DESIGNED BY: **D. Crossley** CHECKED BY: **J. Kelly**
MORRISTOWN SHEET 7 SHEET **82** OF **166**