| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) (LB / FT) 1.75 — 1.88 | SQUARE STEEL (IN) (LB / FT) 2.00 — 2.42 | SQUARE STEEL (IN) (LB / FT) 2.50 — 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) (LB / FT) 3.00 — 7.60 | TUBULAR STEEL Ø (IN) (LB / FT) 3.50 — 9.00 | TUBULAR STEEL Ø (IN) (LB / FT) 4.00 — 10.80 | TUBULAR STEEL Ø (IN) (LB / FT) 5.00 — 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **TROY VT 100** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| NB | 1.430 | A | W1-2R | 30 | 30 | | RIGHT CURVE | | | | | 1 | | | | 2 | | X | | | | | | | | INSTALL 100'+/- NORTH OF ORIGINAL LOCATION | X | | |
| | | A | VW-054L | 30 | 30 | | HIDDEN DRIVE LEFT | | | | | 1 | | | | | | | | | | | | | | | | | E-154 |
| NB | 1.450 | A | W11-6H | 30 | 30 | | HINGED SNOWMOBILE | | | | | | 1 | | X | | | | | | | | | | | | | | |
| NB | 1.550 | A | W11-5 | 30 | 30 | | FARM MACHINERY | | | 1 | | | | X | | | | | | | | | | | | | | | |
| NB | 1.980 | A | W11-4 | 30 | 30 | | CATTLE | | | | | | 1 | | X | | | | | | | | | | | | | | |
| NB | 2.199 | C | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | BONNEAU RD TH-27 | | | |
| | | C | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | | | E-141 |
| NB | 2.040 | D | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | BONNEAU RD TH-27 | | | |
| | | D | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| NB | 2.700 | A | W1-2L | 30 | 30 | | LEFT CURVE | | | | | | 1 | | X | | | | | | | | | | | | | | |
| NB | 2.757 | A | W1-2L | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL 300' NORTH OF ORIGINAL SIGN LOCATION | X | | |
| NB | 2.830 | A | W11-6H | 30 | 30 | | HINGED SNOWMOBILE | | | | | | 1 | | X | | | | | | | | | | | | | | |
| SB | 2.963 | G | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | ROUTHIER RD TH-44 | | | |
| | | G | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | X | | | | | | | | | | | E-141 |
| SB | 2.958 | H | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | ROUTHIER RD TH-44 | | | |
| | | | | | | | SHEET TOTALS | 22.50 SF | 0.00 SF | 1 EA | 0 EA | 2 EA | 8 EA | 0 EA | 0 EA | 6 EA | | 90 FT | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 334.5 | 0.0 | 7.0 | 2.0 | 2.0 | 60 | 0.0 | 0.0 | 55 | | 825.0 | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Moretown-Newport Town VT100**
PROJECT NUMBER: **STPG SIGN(28)**

FILE NAME: **Trov.xls**
PROJECT MANAGER: **N. Averv**
DESIGNED BY: **D. Crossley**
TROY SHEET 4

PLOT DATE: **9/30/2009**
DRAWN BY: **I. Shea**
CHECKED BY: **J. Kelly**