

**GENERAL INFORMATION**

**SYMBOLY LEGEND NOTE**

THE SYMBOLY ON THIS SHEET IS INTENDED TO COVER STANDARD CONVENTIONAL SYMBOLY. THE SYMBOLY IS USED FOR EXISTING & PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROJECT ANNOTATION, AS NOTED ON PROJECT PLAN SHEETS. THIS LEGEND SHEET COVERS THE BASICS. SYMBOLY ON PLANS MAY VARY, PLAN ANNOTATIONS AND NOTES SHOULD BE USED TO CLARIFY AS NEEDED.

**R.O.W. ABBREVIATIONS (CODES) & SYMBOLS**

POINT CODE	DESCRIPTION
CH	CHANNEL EASEMENT
CONST	CONSTRUCTION EASEMENT
CUL	CULVERT EASEMENT
D&C	DISCONNECT & CONNECT
DIT	DITCH EASEMENT
DR	DRAINAGE EASEMENT
DRIVE	DRIVEWAY EASEMENT
EC	EROSION CONTROL
HWY	HIGHWAY EASEMENT
I&M	INSTALL & MAINTAIN EASEMENT
LAND	LANDSCAPE EASEMENT
R&RES	REMOVE & RESET
R&REP	REMOVE & REPLACE
SR	SLOPE RIGHT
UE	UTILITY EASEMENT
(P)	PERMANENT EASEMENT
(T)	TEMPORARY EASEMENT
■	BNDNS BOUND SET
▣	BNDNS BOUND TO BE SET
●	IPNS IRON PIN SET
⊙	IPNS IRON PIN TO BE SET
⊠	CALC EXISTING ROW POINT
○	PROW PROPOSED ROW POINT
[LENGTH]	LENGTH CARRIED ON NEXT SHEET

**COMMON TOPOGRAPHIC POINT SYMBOLS**

POINT CODE	DESCRIPTION
⊕	APL BOUND APPARENT LOCATION
○	BM BENCHMARK
□	BND BOUND
▣	CB CATCH BASIN
⊕	COMB COMBINATION POLE
▣	DITHR DROP INLET THROATED DNC
⊕	EL ELECTRIC POWER POLE
○	FPOLE FLAGPOLE
○	GASFIL GAS FILLER
○	GP GUIDE POST
×	GSO GAS SHUT OFF
○	GUY GUY POLE
○	GUYW GUY WIRE
×	GV GATE VALVE
⊕	H TREE HARDWOOD
△	HCTRL CONTROL HORIZONTAL
▲	HVCTRL CONTROL HORIZ. & VERTICAL
◇	HYD HYDRANT
●	IP IRON PIN
●	IPIPE IRON PIPE
⊕	LI LIGHT - STREET OR YARD
♫	MB MAILBOX
○	MH MANHOLE (MH)
□	MM MILE MARKER
●	PM PARKING METER
□	PMK PROJECT MARKER
○	POST POST STONE/WOOD
⊕	RRSIG RAILROAD SIGNAL
⊕	RRSL RAILROAD SWITCH LEVER
⊕	S TREE SOFTWOOD
⊕	SAT SATELLITE DISH
⊕	SHRUB SHRUB
⊕	SIGN SIGN
⊕	STUMP STUMP
⊕	TEL TELEPHONE POLE
○	TIE TIE
⊕	TSIGN SIGN W/DOUBLE POST
⊕	VCTRL CONTROL VERTICAL
○	WELL WELL
×	WSO WATER SHUT OFF

THESE ARE COMMON VAOT SURVEY POINT SYMBOLS FOR EXISTING FEATURES, ALSO USED FOR PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROPOSED ANNOTATION.

**PROPOSED GEOMETRY CODES**

CODE	DESCRIPTION
PC	POINT OF CURVATURE
PI	POINT OF INTERSECTION
CC	CENTER OF CURVE
PT	POINT OF TANGENCY
PCC	POINT OF COMPOUND CURVE
PRC	POINT OF REVERSE CURVE
POB	POINT OF BEGINNING
POE	POINT OF ENDING
STA	STATION PREFIX
AH	AHEAD STATION SUFFIX
BK	BACK STATION SUFFIX
D	CURVE DEGREE OF (100FT)
R	CURVE RADUIS OF
T	CURVE TANGENT LENGTH
L	CURVE LENGTH OF
E	CURVE EXTERNAL DISTANCE

**UTILITY SYMBOLY**

**UNDERGROUND UTILITIES**

— UT —	UTILITY (GENERIC-UNKNOWN)
— UE —	TELEPHONE
— UC —	ELECTRIC
— UEC —	CABLE (TV)
— UEC —	ELECTRIC+CABLE
— UET —	ELECTRIC+TELEPHONE
— UCT —	CABLE+TELEPHONE
— UECT —	ELECTRIC+CABLE+TELEP.
— G —	GAS LINE
— W —	WATER LINE
— S —	SANITARY SEWER (SEPTIC)

**ABOVE GROUND UTILITIES (AERIAL)**

— AGU —	UTILITY (GENERIC-UNKNOWN)
— T —	TELEPHONE
— E —	ELECTRIC
— C —	CABLE (TV)
— EC —	ELECTRIC+CABLE
— ET —	ELECTRIC+TELEPHONE
— AER E&T —	ELECTRIC+TELEPHONE
— CT —	CABLE+TELEPHONE
— ECT —	ELECTRIC+CABLE+TELEP.
—	UTILITY POLE GUY WIRE

**PROJECT CONSTRUCTION SYMBOLY**

**PROJECT DESIGN & LAYOUT SYMBOLY**

— — — — CZ — — — —	CLEAR ZONE
— — — — — — — —	PLAN LAYOUT MATCHLINE

**PROJECT CONSTRUCTION FEATURES**

▲ — — — — ▲	TOP OF CUT SLOPE
○ — — — — ○	TOE OF FILL SLOPE
⊕ — — — — ⊕	STONE FILL
⊕ — — — — ⊕	BOTTOM OF DITCH
— — — — — — — —	CULVERT PROPOSED
— — — — — — — —	STRUCTURE SUBSURFACE
PDF — — — — PDF	PROJECT DEMARCATION FENCE
BF — — — — BF	BARRIER FENCE
⊗ — — — — ⊗	TREE PROTECTION ZONE (TPZ)
/// — — — — ///	STRIPING LINE REMOVAL
~~~~~	SHEET PILES

**CONVENTIONAL BOUNDARY SYMBOLY**

**BOUNDARY LINES**

— — — — — — — —	TOWN BOUNDARY LINE
— — — — — — — —	COUNTY BOUNDARY LINE
— — — — — — — —	STATE BOUNDARY LINE
— — — — — — — —	PROPOSED STATE R.O.W. (LIMITED ACCESS)
— — — — — — — —	PROPOSED STATE R.O.W.
— — — — — — — —	STATE ROW (LIMITED ACCESS)
— — — — — — — —	STATE ROW
— — — — — — — —	TOWN ROW
— — — — — — — —	PERMANENT EASEMENT LINE (P)
— — — — — — — —	TEMPORARY EASEMENT LINE (T)
— — — — — — — —	SURVEY LINE
— — — — — — — —	PROPERTY LINE (P/L)
SR — — — — SR	SLOPE RIGHTS
6f — — — — 6f	6F PROPERTY BOUNDARY
4f — — — — 4f	4F PROPERTY BOUNDARY
HAZ — — — — HAZ	HAZARDOUS WASTE

**EPSC LAYOUT PLAN SYMBOLY**

**EPSC MEASURES**

ONNOONNOONNO	FILTER CURTAIN
— — — — — — — —	SILT FENCE
— — — — — — — —	SILT FENCE WOVEN WIRE
— — — — — — — —	CHECK DAM
— — — — — — — —	DISTURBED AREAS REQUIRING RE-VEGETATION
— — — — — — — —	EROSION MATTING

**ENVIRONMENTAL RESOURCES**

— — — — — — — —	WETLAND BOUNDARY
— — — — — — — —	RIPARIAN BUFFER ZONE
— — — — — — — —	WETLAND BUFFER ZONE
— — — — — — — —	SOIL TYPE BOUNDARY
— — — — — — — —	T&E THREATENED & ENDANGERED SPECIES
HAZ — — — — HAZ	HAZARDOUS WASTE AREA
AG — — — — AG	AGRICULTURAL LAND
HABITAT — — — —	FISH & WILDLIFE HABITAT
FLOOD PLAN — — — —	FLOOD PLAN
— — — — — — — —	ORDINARY HIGH WATER (OHW)
— — — — — — — —	STORM WATER
— — — — — — — —	USDA FOREST SERVICE LANDS
— — — — — — — —	WILDLIFE HABITAT SUIT/CONN

**ARCHEOLOGICAL & HISTORIC**

— — — — — — — —	ARCH ARCHEOLOGICAL BOUNDARY
HISTORIC DIST — — — —	HISTORIC DISTRICT BOUNDARY
HISTORIC — — — —	HISTORIC AREA
(H)	HISTORIC STRUCTURE

**CONVENTIONAL TOPOGRAPHIC SYMBOLY**

**EXISTING FEATURES**

— — — — — — — —	ROAD EDGE PAVEMENT
— — — — — — — —	ROAD EDGE GRAVEL
— — — — — — — —	DRIVEWAY EDGE
— — — — — — — —	DITCH
— — — — — — — —	FOUNDATION
x — — — — x	FENCE (EXISTING)
□ — — — — □	FENCE WOOD POST
○ — — — — ○	FENCE STEEL POST
— — — — — — — —	GARDEN
— — — — — — — —	ROAD GUARDRAIL
— — — — — — — —	RAILROAD TRACKS
— — — — — — — —	CULVERT (EXISTING)
— — — — — — — —	STONE WALL
— — — — — — — —	WALL
— — — — — — — —	WOOD LINE
— — — — — — — —	BRUSH LINE
— — — — — — — —	HEDGE
— — — — — — — —	BODY OF WATER EDGE
— — — — — — — —	LEDGE EXPOSED

PROJECT NAME: WALDEN  
PROJECT NUMBER: BRF 030-3(5)

FILE NAME: s09b308\_legend.dgn PLOT DATE: 05-DEC-2014  
PROJECT LEADER: C. CARLSON DRAWN BY: R. PELLET  
DESIGNED BY: H. SALLS CHECKED BY: H. SALLS  
CONVENTIONAL SYMBOLY LEGEND SHEET 10 OF 56