

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES						TOTALS	DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	EROSION CONTROL	RAILROAD	FULL C. E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS	
25				25	CY	EARTH BORROW	203.30	EST.			COLD PLANING - BITUMINOUS PAVEMENT	
1				1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N. A. B. I.)	204.22	EST.	30692	SY	MAINLINE - U.S. ROUTE 2	
32100				32100	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	365	1043	SY	SIDERoadS	
220				220	TON	AGGREGATE SHOULDERS, RAP	402.13	4	365	SY	ROUNDING	
133				133	CWT	EMULSIFIED ASPHALT	404.65	1.8	32100	SY	TOTAL	
1				1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N. A. B. I.)	406.50	EST.			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	
3710				3710	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	35	2665	TON	MAINLINE - U.S ROUTE 2 WEARING COURSE (TYPE IVS)	
1				1	LU	AIR VOIDS PAY ADJUSTMENT (N. A. B. I.)	490.31	EST.	91	TON	SIDERoadS (TYPE IVS)	
1				1	LU	MAT DENSITY PAY ADJUSTMENT (N. A. B. I.)	490.32	EST.	919	TON	LEVELING (TYPE IVS)	
1				1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N. A. B. I.)	490.33	EST.	35	TON	ROUNDING	
5				5	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	EST.	3710	TON	TOTAL	
18				18	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.				
5				5	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.				
8				8	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.				
169				169	HR	POWER GRADER RENTAL	608.15	EST.				
169				169	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.				
28				28	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.				
48				48	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.				
88				88	HR	TRUCK RENTAL	608.37	EST.				
48				48	HR	LOADER RENTAL, TYPE I	608.40	EST.				
	10			10	CY	STONE FILL, TYPE I	613.10	EST.				
28				28	EACH	YIELDING MARKER POSTS	619.17	-				
5550				5550	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	3				
25				25	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	-				
1				1	EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-				
6				6	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-				
5450				5450	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-				
9				9	EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-				
1160				1160	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.				
3480				3480	HR	FLAGGERS	630.15	EST.				
			0.4	0.4	LS	FIELD OFFICE, ENGINEERS	631.10	-				
			0.4	0.4	LS	TESTING EQUIPMENT, CONCRETE	631.16	-				
			0.4	0.4	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-				
			1000	1000	DL	FIELD OFFICE TELEPHONE (N. A. B. I.)	631.26	-				
0.4				0.4	LS	MOBILIZATION/DEMOBILIZATION	635.11	-				
1				1	LS	TRAFFIC CONTROL (STP 2905 (I))	641.10	-				

PROJECT NAME: MONTPELIER
PROJECT NUMBER: STP 2905(I)

FILE NAME: p10d116.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10d116qs01.i

PLOT DATE: 26-MAY-2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 10 OF 79