

# QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES					TOTALS	DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	EROSION CONTROL	RAILROAD	FULL C. E.	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS
	110			110	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			TEMPORARY EROSION MATTING
	970			970	EACH	LINE STRIPING TARGETS	646.76	11	191	SY	DITCHING
	80			80	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.	25	SY	GUARDRAIL MTS
	80			80	LB	SEED	651.15	EST.	4	SY	ROUNDING
	500			500	LB	FERTILIZER	651.18	EST.	220	SY	TOTAL
	2			2	TON	AGRICULTURAL LIMESTONE	651.20	EST.			
	2			2	TON	HAY MULCH	651.25	EST.			
	50			50	CY	TOPSOIL	651.35	EST.			
	220			220	SY	TEMPORARY EROSION MATTING	653.20	4			
	385			385	SF	TRAFFIC SIGNS, TYPE A	675.20	2.35			
	115			115	LB	TUBULAR ALUMINUM SIGN POST	675.32	4			
	940			940	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	10			
	83			83	EACH	REMOVING SIGNS	675.50	-			
	12			12	EACH	ERECTING SALVAGED SIGNS	675.60	-			
	7			7	EACH	DELINEATOR WITH STEEL POST	676.10	-			
	1			1	LU	PRICE ADJUSTMENT, FUEL (N. A. B. I.)	690.50	-			
		1		1	LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N. A. B. I.)	900.650	-			
	550			550	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	12			
	20			20	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE 1)	900.680	EST.			

PROJECT NAME: MONTPELIER  
PROJECT NUMBER: STP 2905(1)

FILE NAME: p10d116.dgn  
PROJECT LEADER: JLL  
DESIGNED BY: STANTEC  
IPARM FILE: p10d116qs03.i

PLOT DATE: 26-MAY-2011  
DRAWN BY: STANTEC  
CHECKED BY: STANTEC  
SHEET 12 OF 79