ITEM DETAIL SUMMARY SHEET

LOCATION			GUARDRAIL					MISCELLANEOUS									REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	621.205 S.B. G.R. GALV. W/8' POST LF	621.207 S.B. G.R. GLV./NST W/8' POST LF	621.50 MTS. FLARED EACH	621.60 ANCHOR FOR S.B. RAIL EACH	621.80 REMOVAL & DISPOSAL OF GUARDRAIL LF	203.30 EARTH BORROW CY	402.13 AGGREGATE SHOULDERS, RAP TON	604.40 CHAN ELEV OF DI, CB OR MH EACH	604.412 REHAB DI, CB, OR MH, CLASS I EACH	604.415 REHAB DI, CB, OR MH, CLASS II EACH	604.42 CHANGING ELEV. OF SEWER MH EACH	619.17 YIELDING MARKER POSTS EACH	653.20 TEMP. EROSION MATTING SY	676.10 DELINEATOR WITH STEEL POST EACH	
U.S ROUTE 2																	
0+00	84+79.68								216	5	18	5	8	28			QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER, FOR STRUCTURE LOCATIONS, SEE DRAINAGE & STRUCTURE INVENTORY & DETAIL SHEET.
0+00		RT			1		37.5	25							25	1	CONNECT TO EXISTING GUARDRAIL.
16+02.5	27+52.5	RT	1199			2	1062.5									2	INSTALL ANCHORS AT STA. 16+02.5, RT AND 27+52.5, RT. REFER TO GUARDRAIL DETAIL SHEET FOR REDUCED SPACING LOCATIONS.
26+41	27+53.5	LT	116.5			2	112.5									2	INSTALL ANCHORS AT STA. 26+41, LT AND 27+53.5, LT.
37+03.5	79+41	RT	4231.5	25		2	4237.5									2	INSTALL ANCHORS AT STA. 37+03.5, RT AND 79+41 RT. REFER TO GUARDRAIL DETAIL SHEET FOR REDUCED POST SPACING LOCATIONS. INSTALL STEEL BEAM GUARDRAIL GALVANIZED/NESTED FROM STA. 79+03.5 TO 79+28.5, RT, SEE GUARDRAIL DETAIL SHEET.
SHEET SUBTOTALS:			5547	25	1	6	5450	25	216	5	18	5	8	28	25	7	
ROUNDING			3	-	-	-	-	-	4	-	-	-	-	-	-	-	
TOTAL			5550	25	1	6	5450	25	220	5	18	5	8	28	25*	7	

*THESE TOTALS ARE CARRIED FORWARD TO THE DETAILED SUMMARY OF QUANTITIES ON THE QUANTITY SHEETS.

ITEM DETAIL SUMMARY SHEET

PROJECT NAME: MONTPELIER
PROJECT NUMBER: STP 2905(I)

FILE NAME: p10d116.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p10d116idss.i

PLOT DATE: 26-MAY-2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 13 OF 79