STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 04

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
MONTPELIER STATE HIGHWAY (CONT.)																																				
38+92, RT	JCT 2	1	30	21	4.38						1						X	X																M2-1		SEE FHWA SHS
		1	36	36	9.00																													MI-4		SEE FHWA SHS
39+29, LT		1	48	48	16.00						2						X	X																W10-3		SEE FHWA SHS
	SHEET TOTAL				29.38												45																			
	TSS SHEET 1 SUBTOTALS				48.00	427.00	1									30	17			61	-		1		153										
	TSS SHEET 2 SUBTOTALS				97.05	26.00	-									85	102			-	72		-		-										
	TSS SHEET 3 SUBTOTALS				104.42	-	-									65	90			24	-		-		-										
	TSS SHEET 4 SUBTOTALS				29.38	-	-									-	45			-	-		-		-										
	PROJECT SUBTOTALS				278.85	453.00	1									180	254			85	72		1		153										
	ROUNDING				1.15	7.00	-									2	4			5	3		-		2										
	PROJECT TOTALS				280.00	460	1									182	258			90	75		1		155										
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
																182	258			90	75				155										
	TOTALS				SF 280	SF 460	EA. 1	EA.				FT			FT 440					LB 165			EA. 1	LB 155			EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: MONTPELIER
PROJECT NUMBER: NH 2901(1)

FILE NAME: p09b316.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p09b316tss04.i

PLOT DATE: 26-MAY-2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 53 OF 79