ITEM DETAIL SUMMARY SHEET

LOCATION			GUARDRAIL			MISCELLANEOUS														REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	621.20 S.B. G.R. GALV.	621.50 MTS. FLARED	621.80 REMOVAL & DISPOSAL OF GUARDRAIL	203.30 EARTH BORROW	402.13 AGGREGATE SHOULDERS, RAP	604.40 CHAN ELEV OF DI, CB OR MH	604.412 REHAB DI, CB, OR MH, CLASS I	604.415 REHAB DI, CB, OR MH, CLASS II	616.35 TREATED TIMBER CURB	619.17 YIELDING MARKER POSTS	653.20 TEMPORARY EROSION MATTING	676.10 DELINEATOR WITH STEEL POST	676.12 REMOVAL OF EXIST. DELINEATOR						
			LF	EACH	LF	CY	TON	EACH	EACH	EACH	LF	EACH	SY	EACH	EACH						
MONTPELIER JCT ST. HWY.																					
0+31.68	36+59.04	LT&RT					127	5	3	1		6									QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER, FOR STRUCTURE LOCATIONS, SEE MISCELLANEOUS DETAIL SHEET.
21+04.0	26+79.0	RT	500	2		50							50	2							INSTALL M.T.S., FLARED STA. 21+04.0 TO 21+41.5 & STA. 26+41.5 TO 26+79.0.
RAMP M	MAINLINE																				
0+98.0	8+42.0	RT	862.5	1	900	25					46		25	1	1						CONNECT TO GUARDRAIL @ RAMP M STA. 0+98.0. INSTALL M.T.S., FLARED STA. 8+04.5 TO 8+42.0. INSTALL TREATED TIMBER CURB @ RAMP M STA. 0+98 TO 1+44.
SHEET SUBTOTALS:			1362.5	3	900	75	127	5	3	1	46	6	75	3	1						
ROUNDING:			12.5	-	-	5	3	-	-	-	4	-	-	-	-						
TOTALS:			1375	3	900	80	130	5	3	1	50	6	75*	3	1						

*THESE TOTALS ARE CARRIED FORWARD TO THE DETAILED SUMMARY OF QUANTITIES ON THE QUANTITY SHEETS.

ITEM DETAIL SUMMARY SHEET

PROJECT NAME: MONTPELIER
PROJECT NUMBER: STP 2902(I)

FILE NAME: p09b318.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p09b318idss01.i

PLOT DATE: 26-MAY-2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 66 OF 79