STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 03

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MONTPELIER JCT STATE HIGHWAY (CONTINUED)																																				
35+00, RT	PAVEMENT ENDS	1	36	36	9.00						2					X		X															W8-3		SEE FHWA SHS
36+59, LT	STATE HIGHWAY BEGINS	1	24	18	3.00						1					X		X															VR-039		E-141
36+59, RT	STATE HIGHWAY ENDS	1	24	18	3.00						1					X		X															VR-038		E-141
MONTPELIER JCT STATE HIGHWAY SLIP RAMP M 1+46, LT		1	30	30	6.25						1					X		X															W3-2		SEE FHWA SHS
3+02, RT	YIELD; DO NOT ENTER B-B	1 1	36 36	36 36	9.00 9.00						1					X		X															R1-2 R5-1		SEE FHWA SHS SEE FHWA SHS
MONTPELIER JCT STATE HIGHWAY SLIP RAMP N 102+67, RT	YIELD; 9390 1211 0030 B-B	1 1	36 6	36 10	9.00 0.42						1					X		X															R1-2		SEE FHWA SHS E-138
	SHEET TOTAL				48.67											106																			
	TSS SHEET 1 SUBTOTALS				74.76										8	136	15																		
	TSS SHEET 2 SUBTOTALS				75.36										-	199																			
	TSS SHEET 3 SUBTOTALS				48.67										-	106																			
	PROJECT SUBTOTALS				198.79										8	441	15																		
	ROUNDING				1.21										2	4	-																		
	PROJECT TOTALS				200										10	445	15																		
												FT	FT	FT	FT 10	FT 445	FT 15		EA	LB	LB	LB		LB	LB	LB	LB								
	TOTALS				SF 200	SF	EA.	EA.				FT			FT 470					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: MONTPELIER
PROJECT NUMBER: STP 2902(1)

FILE NAME: p09b318.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p09b318tss03.i

PLOT DATE: 26-MAY-2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 78 OF 79