

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	LANDSCAPING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							2800				2800		CY	COMMON EXCAVATION	203.15	8			
							150				150		CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28	8			
							1075				1075		CY	SAND BORROW	203.31	12			
							62				62		CY	TRENCH EXCAVATION OF EARTH	204.20	1			
							2				2		CY	TRENCH EXCAVATION OF ROCK	204.21	-			
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
							6				6		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-			
							1470				1470		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	5			
							14				14		CWT	EMULSIFIED ASPHALT	404.65	1			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							120				120		LB	REINFORCING STEEL, LEVEL I	507.11	1			
							1				1		GAL	WATER REPELLENT, SILANE	514.10	0.6			
							2				2		CY	CONCRETE, CLASS B	541.25	0.5			
							44				44		LF	18" CPEP(SL)	601.2615	-			
							2				2		EACH	18" CPEPES	601.7015	-			
							212				212		LF	CLEANING CULV. PIPE, IN-PLACE [0 TO 24 IN., INCL.]	601.995	-			
							1				1		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							10				10		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							1				1		HR	TRUCK RENTAL	608.37	EST.			
							140				140		MGAL	DUST CONTROL WITH WATER	609.10	4			
							750				750		LF	REMOVAL OF EXISTING CURB	616.41	7			
							260				260		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	2			
							5				5		EACH	YIELDING MARKER POSTS	619.17	-			
							280				280		LF	REMOVAL OF EXISTING FENCE	620.55	-			
							90				90		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							300				300		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			
							28				28		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17	-			
														BEGIN OPTION AA					
							2100				2100		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	14			
							2100				2100		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	14			
														END OPTION AA					
														BEGIN OPTION BB					
							200				200		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	6			
							200				200		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	6			

PROJECT NAME: BRADFORD  
 PROJECT NUMBER: CMG PARK (33)  
 FILE NAME: z09K252frm.dgn PLOT DATE: 5/22/2014  
 PROJECT LEADER: M. FOISY DRAWN BY: P. ARMATA  
 DESIGNED BY: I. MAYNARD CHECKED BY: G. SANTY  
 QUANTITY SHEET 1 SHEET 4 OF 33

