STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B" REMOVE	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
GEORGIA																																				
US ROUTE 7	PARK - RIDE →	1	30	36	7.50	1					1					X		X															INSTALL NEW SIGN IN EXISTING LOCATION	TSD-1	
US ROUTE 7	PARK - RIDE ←	1	30	36	7.50	1					1					X		X															INSTALL NEW SIGN IN EXISTING LOCATION	TSD-1	
SKUNK HILL ROAD	PARK - RIDE ←	1	30	36	7.50	1					1					X		X															INSTALL NEW SIGN IN EXISTING LOCATION	TSD-1	
PARK-AND-RIDE	PROHIBITED 1500 TRESPASS TOWS ON VEHICLES LAW ENFORCEMENT	1 1	30 24	24 30	5.00 5.00	1					1						X	X															INSTALL NEW SIGNS FACING VEHICLES ENTERING PARK-AND-RIDE VR-023B	TSD-1	E-144
PARK-AND-RIDE	CARPOOL INFO Go vermont	1	30	30	6.25	1					1					X		X															LOCATE SIGN 15' WEST OF LIGHT POLE #4-3A ALONG NORTH EDGE OF PARK-AND-RIDE FACING LOT ENTRANCE	TSD-1	
PARK-AND-RIDE	SELECTED PARKING	1	12	18	1.50	1					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-2	
PARK-AND-RIDE	STOP	1	30	30	6.25						1					X		X															INSTALL NEW SIGN AT EXIT OF PARK-AND-RIDE RI-1		SEE FHWA SHS
PARK-AND-RIDE	BUS STOP BUS SCHEDULE					1	1 1 1				1					X		X															MOUNT SALVAGED SIGNS ON A NEW POST		
												FT	FT	FT	FT	FT 105	FT 15.4		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT 120.4					LB			EA.	LB				EA.	EA.	LB					
TOTALS					SF 46.50	SF 9	EA. ~~2~~ 3	SF																												

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE
PROJECT NUMBER: CMG PARK(34)

FILE NAME: ...\Plot Files\TSS08_ptf.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: E. ALLING
GEORGIAtss08

PLOT DATE: 6/21/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 46 OF 69