STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B" REMOVE	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 (1.88)	2.0 (2.42)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (In) lb/ft FOUND-ATION	3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
MORRISVILLE																																			
VT ROUTE 100	PARK - RIDE	1	30	36	7.50	1					1					X		X															INSTALL NEW SIGN IN EXISTING LOCATION	TSD-1	
VT ROUTE 100	PARK - RIDE	1	30	36	7.50	1					1					X		X															INSTALL NEW SIGN IN EXISTING LOCATION	TSD-1	
PARK-AND-RIDE		1 1	30 24	24 30	5.00 5.00	1					1						X	X															INSTALL NEW SIGNS AT EXISTING LOCATION VR-023B	TSD-1	E-144
PARK-AND-RIDE	CARPOOL INFO	1	30	30	6.25						1					X		X															LOCATE NEW SIGN 25' WEST OF BUS STOP SIGN	TSD-1	
PARK-AND-RIDE	RESERVED COMMUTER PARKING	1	12	18	1.50	1					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-3	
PARK-AND-RIDE		1 1	12 12	18 6	1.50 0.50	2					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST R7-8a	TSD-2	SEE FHWA SHS
PARK-AND-RIDE	RESERVED COMMUTER PARKING	1	12	18	1.50	1					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-3	
PARK-AND-RIDE		1	12	18	1.50	1					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-2	
PARK-AND-RIDE		1	24	24	4.00	1					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST R8-3		SEE FHWA SHS
PARK-AND-RIDE		1	12	18	1.50	1					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-2	
PARK-AND-RIDE		1	12	18	1.50	1					1					X		X															REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-2	
												FT	FT	FT	FT	FT 150	FT 15.4		EA	LB	LB	LB		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		**TOTALS**			SF 44.75	SF 11	EA.	SF				FT			FT 165.4					LB			EA.	LB				EA.	EA.	LB					

PROJECT NAME: STATEWIDE
PROJECT NUMBER: CMG PARK(34)

FILE NAME: ...\Plot Files\TSS13_ptf.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: E. ALLING
MORRISVILLEtss13

PLOT DATE: 6/21/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 51 OF 69