STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 26

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B" REMOVE	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75 (1.88)	SQUARE STEEL (In) lb/ft 2.0 (2.42)	SQUARE STEEL (In) lb/ft 2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (In) lb/ft 4.0 MOD (1.7)	FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (In) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (In) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (In) lb/ft 5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
WEST DANVILLE																																				
US ROUTE 2	PARK - RIDE	1	30	36	7.50	1			X																									INSTALL NEW SIGN IN EXISTING LOCATION BELOW RETAINED SIGNS ON RETAINED POST	TSD-1	
MEDIAN ISLAND		1 1	24 18	30 18	5.00 2.25	2					1					X		X																REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST R4-1 & OM1-1		SEE FHWA SHS SEE FHWA SHS
MEDIAN ISLAND		1	12	18	1.50	1					1					X		X																REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-2	
PARK-AND-RIDE		1	12	18	1.50	1					1					X		X																REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST	TSD-2	
MEDIAN ISLAND	B-B	1 1 1 1	30 30 24 24	30 30 12 12	6.25 6.25 2.00 2.00	4					1					X		X																REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST 2 (W11-2 & W16-7P) BACK-TO-BACK (FLUORESCENT YELLOW-GREEN)		SEE FHWA SHS SEE FHWA SHS SEE FHWA SHS SEE FHWA SHS
PARK-AND-RIDE	CARPOOL INFO	1	30	30	6.25						1					X		X																LOCATE NEW SIGN ALONG BACK EDGE OF PARK-AND-RIDE IN A LOCATION EASILY VISIBLE FROM THE LOT	TSD-1	
MEDIAN ISLAND		1	18	18	2.25	1					1					X		X																REMOVE AND REPLACE IN KIND WITH NEW SIGN(S) AND POST OM1-1		SEE FHWA SHS
PARK-AND-RIDE						3	~~1~~ 2				1					X		X																SALVAGE SIGN IN EXISTING LOCATION WITH NEW POST		
PARK-AND-RIDE	$500 FINE THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1					X		X																PLACE NEW SIGN 15' EAST OF LOCATION OF EXISTING SIGN WITH NEW POST VR-023B		E-144
PARK-AND-RIDE	VSTIC	1	30	24	5.00	2	1				1						X	X																INSTALL NEW SIGN IN EXISTING LOCATION WITH SALVAGED SIGN ON A NEW POST	TSD-1	
US ROUTE 2	PARK - RIDE	1	30	36	7.50				X																									INSTALL NEW SIGN IN EXISTING LOCATION BELOW RETAINED SIGNS ON RETAINED POST	TSD-1	
												FT	FT	FT	FT	FT 120.4	FT 15		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT 135.4					LB			EA.	LB				EA.	EA.	LB					
TOTALS					SF 60.25	SF 15	EA. ~~2~~ 3	SF																												

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: STATEWIDE
PROJECT NUMBER: CMG PARK(34)

FILE NAME: ...\Plot Files\TSS25_ptf.dgn
PROJECT LEADER: G. GOYETTE
DESIGNED BY: E. ALLING
WESTDANVILLEtss26

PLOT DATE: 6/21/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 64 OF 69