








DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	SHSM	PROJECT SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
<b>SWANTON VT105 EB</b>							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS							
			A	W1-7	24	12	<---> DOUBLE ARROW						1																
			A	W11-15a	30	30		6.25						1		X										X			
			A	W16-7pL	24	12		2.00																		X			
EB	1.997		A	M3-2	24	12		2.00						1		X								GREEN ON WHITE. INSTALL 40' +/- WEST OF MAILBOX #2101		X			
			A	M1-5A	30	24		5.00																			E-136B		
EB	2.035		A	R2-1	24	30		5.00						1		X								INSTALL 290' +/- WEST OF MAILBOX #2112		X			
EB	3.086		A	W1-2MR	30	30	MODIFIED RIGHT CURVE						1			X													
EB	3.110		A	W1-10R	36	36		9.00						2		X								INSTALL 125' +/- EAST OF EXISTING LOCATION		X			
EB	3.340		A	R2-1	24	30							1			X													
			A	R2-1	24	30		5.00						1		X										X			
EB	3.450		A	W11-6	30	30							1			X													
			A	W11-6H	30	30		6.25						1		X								INSTALL IN CLOSED POSITION			E-153		
<b>SIGN SUMMARY SHEET</b>							<b>SHEET TOTALS</b>	40.50	0.00	0	0	0	4	0	0	7	105.0	0	0.0	0.0	0.0	0.0			PROJECT NAME: <b>St Albans - Berkshire</b> PROJECT NUMBER: <b>STPG SIGN(36)</b>				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	EA	LB	LB	LB	LB			FILE NAME: <b>SwantonEB.xls</b> PROJECT MANAGER: <b>A. Gamble</b> DESIGNED BY: <b>T. Guazzoni</b> SWANTON EB SHEET 2	PLOT DATE: <b>5/17/2011</b> DRAWN BY: <b>T. Guazzoni</b> CHECKED BY: <b>A. Gamble</b> SHEET <b>29</b> OF <b>109</b>			
VERMONT AGENCY OF TRANSPORTATION							<b>TOWN DIRECTIONAL TOTALS</b>	65.3	0.0	0	0	0	13	0	0	13	195.0	0		0.0									