DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 / 2.00 / 2.50 (LB / FT) 1.88 / 2.42 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 / 3.50 / 4.00 / 5.00 (LB / FT) 7.60 / 9.00 / 10.80 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ENOSBURG VT105 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN														"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.000	C	VD-024	60	7.5								3 ~~1~~		X									
		C	VD-024	72	10			5.00								2	X					4	
		C	VD-700	6	10			0.42															E-138
		C	VD-700	6	10			0.42															E-138
EB	0.044	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X									
		A	W3-5	36	36			9.00								2	X					X		
EB	0.070	A	VW-622A	36	36		RECREATIONAL TRAIL						1		X									
		A	W1-7	24	12		<----> DOUBLE ARROW						1											
		A	W11-15a	30	30			6.25								1	X					X	
		A	W16-7pL	24	12			2.00														X		
EB	0.082	A	VD-018	30	18								1		X									
		A	VD-018	30	18			3.75								1	X						7	
EB	0.100	A	VR-072	24	30								1		X									
		A	VR-072	24	30			5.00								1	X						7	
EB	0.120	A	R2-1	24	30								1		X									
							SHEET TOTALS	31.84	0.00	0	0	0	~~9~~ 7	0	0	7	105.0		0	0.0	0.0	0.0	0.0			
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB			
							TOWN DIRECTIONAL TOTALS	393.9	0.0	25	4	4	94	0	0	58	870.0		2	235.6						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **St Albans - Berkshire**
PROJECT NUMBER: **STPG SIGN(36)**

FILE NAME: **EnosburgEB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
DRAWN BY: **T. Guazzoni**
CHECKED **A. Gamble**
PLOT DATE: **5/17/2011**
ENOSBURG EB SHEET 1
SHEET **66** OF **109**