DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ENOSBURG VT105 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	D3-1	UNK	UNK								1																
		A	D3-1	UNK	UNK								1																
		C	M3-2	24	12		WEST						1																
		C	M6-1R	21	15		RIGHT						1																
		C	D3-1	24	8			1.33																	INSTALL ABOVE STOP SIGN		6	
		A	D3-1	24	8			1.33																	INSTALL ABOVE STOP SIGN		6	
		A	R1-1	30	30			6.25								1		X							MAIN ST (VT105/108)	X		
EB	0.695	B	M3-4	24	12			2.00								1		X							GREEN ON WHITE. INSTALL SIGNS DIRECTLY ACROSS FROM INSERSECTION FACING WB TRAFFIC	X		
		B	M1-5	30	24			5.00																				E-136B
		B	M6-1R	21	15			2.19																	GREEN ON WHITE	X		
EB	0.710	A	M3-2	24	12			2.00								1		X							INSTALL SIGNS 160' +/- WEST OF EXISTING LOCATION. GREEN ON WHITE	X		
		A	M1-5	30	24			5.00																#1B				E-136B
		A	M3-1	24	12			2.00																	GREEN ON WHITE	X		
		A	M1-5	30	24			5.00																				E-136B
EB	0.740	A	M3-2	24	12		EAST						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	32.10	0.00	0	0	0	5	0	0	3		45.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	393.9	0.0	25	4	4	94	0	0	58		870.0		2		235.6						

PROJECT NAME: **St Albans - Berkshire**
PROJECT NUMBER: **STPG SIGN(36)**
FILE NAME: **EnosburgEB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
ENOSBURG EB SHEET 6
PLOT DATE: **5/17/2011**
DRAWN BY: **T. Guazzoni**
CHECKED **A. Gamble**
SHEET **71** OF **109**