DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ENOSBURG VT105 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M1-5	30	24		VERMONT 105						1																
		A	M3-1	24	12		NORTH						1																
		A	M1-5	30	24		VERMONT 108						1																
EB	0.750	A	W11-2	30	30		PEDESTRIAN			1				X															
		A	W16-7pL	24	12		LEFT DIAGONAL ARROW			1																			
EB	0.755	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X									DICKINSON AVE (TH-106)		7	
EB	0.760	C	D3-1	UNK	UNK								1																
		A	D3-1	UNK	UNK								1																
		C	D3-1	24	8		Main St	1.33																			INSTALL ABOVE STOP SIGN		6	
		A	D3-1	36	8		Dickinson Ave	2.00																			INSTALL ABOVE STOP SIGN		6	
		D	R1-1	30	30		STOP			1				X													DICKINSON AVE (TH-106)			
EB	0.815	A	VW-622A	36	36		RECREATIONAL TRAIL						1		X														
		A	VW-622P	24	18		ALL SEASON PLAQUE						1																
		A	UNK.	UNK	UNK		SHUTTLE SIGN						1														RETURN SIGN TO VILLAGE			
EB	0.835	A	W11-2	30	30		PEDESTRIAN			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	8.33	0.00	4	0	0	8	0	0	1		15.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	393.9	0.0	25	4	4	94	0	0	58		870.0		2		235.6							

PROJECT NAME: **St Albans - Berkshire**
PROJECT NUMBER: **STPG SIGN(36)**

FILE NAME: **EnosburgEB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
ENOSBURG EB SHEET 7

PLOT DATE: **5/17/2011**
DRAWN BY: **T. Guazzoni**
CHECKED **A. Gamble**
SHEET **72** OF **109**