DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ENOSBURG VT105 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	1.335	A	M3-2	24	12		EAST						1		X													
		A	M1-5	30	24		VERMONT ROUTE 105						1															
EB	1.355	A	W11-2	30	30		PEDESTRIAN			1				X														
		A	W16-7pL	24	12		LEFT DIAGONAL ARROW			1																		
EB	1.355	C	D3-1	UNK	UNK								1															
		A	D3-1	UNK	UNK								1															
		C	D3-1	24	8		Elm St	1.33																		INSTALL ABOVE STOP SIGN		6	
		A	D3-1	36	8		Pleasant St	2.00																		INSTALL ABOVE STOP SIGN		6	
		A	R1-1	30	30		STOP	6.25								1		X								INSTALL GATE POSTED STOP SIGN ON RT SIDE OF PLEASANT ST, 10' +/- AWAY FROM UTILITY POLE	X		
EB	1.355	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								PLEASANT ST. INSTALL SIGN ON RT SIDE OF PLEASANT ST		7	
EB	1.365	D	R1-1	30	30		STOP	6.25								1		X								PLEASANT ST. INSTALL SIGN 50' BEFORE INTERSECTION WITH VT105 ON PLEASANT ST	X		
EB	1.470	A	D1-1A	54	7.5								1		X													
		A	VD1-1A	72	12		← Berkshire 4	6.00								2		X										4	
			END CLASS 1 SECTION - VILLAGE OF ENOSBURG FALLS																										
EB	1.519	B	VR-039	24	18		STATE HIGHWAY BEGINS			1				X														
							SHEET TOTALS	26.83	0.00	3	0	0	5	0	0	5		75.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	393.9	0.0	25	4	4	94	0	0	58		870.0		2		235.6						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **St Albans - Berkshire**
PROJECT NUMBER: **STPG SIGN(36)**

FILE NAME: **EnosburgEB.xls** PLOT DATE: **5/17/2011**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED **A. Gamble**
ENOSBURG EB SHEET 11 SHEET **76** OF **109**