DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
																	1.75	2.00	2.50		3.00	3.50	4.00	5.00					
																	(LB / FT)				(LB / FT)								
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.88	2.42	3.35	FOUNDATION	7.60	9.00	10.80	14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
ENOSBURG VT105 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M6-4	21	15		<---> DOUBLE						1																
		F	W11-15A	30	30			6.25								1		X									X		
		F	W16-7pL	24	12			2.00																			X		
WB	0.120	F	R2-1	24	30								1		X														
		F	R2-1	24	30			5.00								~~1~~		X									X		
WB	0.120	F	VR-072	24	30								1		X														
		F	VR-072	24	30			5.00								1		X										7	
WB	0.110	G	VR-017	24	30							1	2 ~~1~~		X														
		G	VR-017	24	30			5.00								1		X								ORCHARD ST (TH-8)		7	
WB	0.090	H	R1-1	24	24							2	3 ~~1~~		X														
		H	R1-1	30	30			6.25								1		X								ORCHARD ST (TH-8) INSTALL SIGN IN GRASS ISLAND	X		
WB	0.085	H	R1-1	24	24							1	2 ~~1~~		X														
		H	R1-1	30	30			6.25								1		X								ORCHARD ST (TH-8) INSTALL SIGN ON LEFT SIDE OF ORCHARD ST	X		
							SHEET TOTALS	35.75	0.00	0	0	~~0~~ 4	~~6~~ 10	0	0	6		90.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	359.7	0.0	23	0	0	89	0	0	51		765.0		2		171.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **St Albans - Berkshire**
PROJECT NUMBER: **STPG SIGN(36)**

FILE NAME: **EnosburgWB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
ENOSBURG WB SHEET 13

PLOT DATE: **5/17/2011**
DRAWN BY: **T. Guazzoni**
CHECKED **A. Gamble**
SHEET **93** OF **109**