| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) SLIP BASE ~~9.00~~ | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **BERKSHIRE VT 105 EB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | | A | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | D1-1A | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | VD1-1A | 72 | 12 | | | 6.00 | | | | | | | | 2 | | X | | | | | | | | | 4 | |
| | | A | VD1-1A | 72 | 12 | | Richford 5<br>Berkshire 4 | 6.00 | | | | | | | | | | | | | | | | | | | 4 | |
| | | A | VD1-1A | 72 | 12 | | Montgomery 5 | 6.00 | | | | | | | | – | | | | | | | | | | | 4 | |
| EB | 0.950 | A | M3-1 | 24 | 12 | | ROUTE MARKERS (9) | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M6-1 | 21 | 15 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M3-2 | 24 | 12 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M1-5 | 30 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M6-3 | 21 | 15 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M3-3 | 24 | 12 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M5-1 | 21 | 15 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M3-1 | 24 | 12 | | | 2.00 | | | | | | | | 2 | | | X | | | 2 | | | #3C | BLACK ON WHITE. INSTALL ON 2 1/2" SLIP BASES | X | 6 | |
| | | | | | | | SHEET TOTALS | 20.00 | 0.00 | 0 | 0 | 0 | 11 | 0 | 0 | 4 | 60.0 | | | 0 | 0.0 | 2 ~~0.0~~ | 0.0 | 0.0 | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | EA | LB | LB | LB | LB | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 235.4 | 0.0 | 0 | 0 | 0 | 53 | 0 | 0 | 40 | 600.0 | | | 0 | 0.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: St Albans - Berkshire
PROJECT NUMBER: STPG SIGN(36)
FILE NAME: Berkshire EB.xls
PROJECT MANAGER: A. Gamble
DESIGNED BY: T. Guazzoni
CHECKED BY: A. Gamble
PLOT DATE: 5/17/2011
DRAWN BY: T. Guazzoni
BERKSHIRE EB SHEET 3
SHEET 96 OF 109