DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			FOUNDATION	TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35		3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
BERKSHIRE VT 105 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M1-5	30	24			5.00																				E-136B
EB	1.250	A	VW-622B	36	36								1		X														
		A	W1-7	21	15								1																
		A	W11-15a	30	30			6.25								1		X									X		
		A	W16-7pL	24	12			2.00								–											X		
EB	1.390	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		X									X		
EB	1.760	A	VW-092	30	30								0 ~~1~~		0 ~~X~~														
		A	VW-092	36	36			9.00								2		X										E-150	
EB	1.890	C	VR-017	24	24								1		X														
		C	VR-017	24	30			5.00								1		X									RIVER RD (TH-46)		7	
EB	1.880	D	R1-1	30	30							~~3~~	~~4~~ ~~1~~		X														
		D	R1-1	30	30			6.25								1		X									RIVER RD (TH-46)	X		
EB	1.890	A	VW-092	30	30								1		X														
		A	VW-092	36	36			9.00								2		X										E-150	
							SHEET TOTALS	47.50	0.00	0	0	~~0~~ 3	~~7~~ 9	0	0	8		120.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	235.4	0.0	0	0	0	53	0	0	40		600.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **St Albans - Berkshire**
PROJECT NUMBER: **STPG SIGN(36)**

FILE NAME: **BerkshireEB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
CHECKED **A. Gamble**
BERKSHIRE EB SHEET 5

PLOT DATE: **5/17/2011**
DRAWN BY: **T. Guazzoni**
SHEET **98** OF **109**