

COMPOSITE QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES								TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
STP 2913(1)				NH 2948(1)				GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
ROADWAY (MAJOR COLLECTOR)	TRAINING (MAJOR COLLECTOR)	BRIDGE (MAJOR COLLECTOR)	FULL C.E. ITEMS (MAJOR COLLECTOR)	ROADWAY (PRINCIPAL ARTERIAL)	FULL C.E. ITEMS (PR ARTERIAL)											
60				1			61		TON	HAY MULCH	651.25	EST.				
135				25			160		CY	TOPSOIL	651.35	EST.				
1650							1650		SY	GRUBBING MATERIAL	651.40	24.8				
10300				500			10800		SY	TEMPORARY EROSION MATTING	653.20	91.8				
2950							2950		LF	EROSION LOG	653.60	25				
18				240			258		SF	TRAFFIC SIGNS, TYPE A	675.20	2.49				
				590			590		LB	TUBULAR STEEL SIGN POST	675.33	3				
240				450			690		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-				
				6			6		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-				
20				68			88		EACH	REMOVING SIGNS	675.50	-				
20				10			30		EACH	ERECTING SALVAGED SIGNS	675.60	-				
60				20			80		EACH	DELINEATOR WITH STEEL POST	676.10	4				
				20			20		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-				
15							15		EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15	-				
				1			1		EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION	678.15	-				
1				1			2		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-				
120500							120500		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	1141				
2625				440			3065		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	17				
120500							120500		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	1141				
				50			50		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.				
43300				3380			46680		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	503				
1800							1800		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	12				
140							140		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	-				
750				390			1140		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	13				
1535							1535		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	15				

PROJECT NAME: WEATHERSFIELD
 PROJECT NUMBER: STP 2913(I) / NH 2948(I)
 FILE NAME: I0c228.dgn PLOT DATE: 2/7/2013
 PROJECT LEADER: PTS DRAWN BY: WWG
 DESIGNED BY: NULL CHECKED BY: PTS
 IPARM FILE NAME: pI0c228.I3 SHEET 13 OF 234