DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
MORRISTOWN EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	D2-1	72	12			6.00																			4	
EB	1.004	A	R2-1	24	30		SPEED LIMIT 40			1				X														
EB	1.020	C	VR-017	24	30								1		X											MUNSON AVE TH-85			
		C	VR-017	24	30			5.00								1		X										E-141
EB	1.025	D	R1-1	30	30		STOP			1				X													MUNSON AVE TH-85			
EB	1.113	A	R2-1	24	30		SPEED LIMIT 50				1	1			X	1		X										
EB	1.200	A	VM-607	36	30		GRAND ARMY OF THE REPUBLIC			1				X														
EB	1.359	C	VR-017	24	30		LLL 24,000 LBS			1				X													HOULE AVE TH-89			
EB	1.365	D	R1-1	30	30		STOP			1				X														
EB	1.630	C	VR-017	24	30								1		X											HARREL ST TH-16			
		C	VR-017	24	30			5.00								1		X										E-141
EB	1.630	D	R1-1	30	30								1		X											HARREL ST TH-16			
		D	R1-1	30	30			6.25								1		X									X	
EB	1.764	A	S3-1	30	30		SCHOOL BUS STOP AHEAD			1				X														
EB	2.400	A	M2-1	21	15								1		X													
							SHEET TOTALS	22.25 SF	0.00 SF	6 EA	1 EA	1 EA	4 EA	0 EA	0 EA	4 EA		60 FT										
							TOWN DIRECTIONAL TOTALS	143.7	0.0	27.0	10.0	10.0	31	0.0	0.0	27		405.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE NORTHEAST**
PROJECT NUMBER: **STPG SIGN (29)**

FILE NAME: **MORRISTOWN EB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **D. CROSSLEY**
MORRISTOWN VT 15 EB 4

PLOT DATE: **8/18/2010**
DRAWN BY: **D. CROSSLEY**
CHECKED BY: **A. GAMBLE**
SHEET **13** OF **138**