DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
WOLCOTT EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHS"-STANDARD HIGHWAY SIGNS			
EB	5.060	D	R1-1	24	24		STOP						1		X										FLAT IRON RD TH-34			
		D	R1-1	30	30			6.25								1		X								X		
EB	5.692	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X										TURCOTTE RD TH-36			
		C	VR-017	24	30			5.00								1		X										E-141
EB	5.700	D	R1-1	30	30		STOP	6.25			4	4			X	1		X							TURCOTTE RD TH-36			
EB	6.490	A	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X													
EB	6.530	A	W1-2 L	30	30			6.25								1		X							INSTALL AT MID POINT OF CIRCULAR DRIVE 210'+/- EAST OF REMOVED VW-054R SIGN	X		
EB	6.840	A	VW-202	30	30		TRUCKS ENTERING						1		X													
EB	7.023	C	VD-024	60	7.5								1		X													
		C	VD-024	72	10		Hardwick / Wolcott / Caledonia Co. / Lamoille Co.	5.00								2		X										4	
		C	VD-025	72	10		0150 0305 0000 / 0150 0810 0702	5.00																			4	
		C	VD-700	6	10			0.42																			4	
		C	VD-700	6	10			0.42																			4	
							TOWN DIRECTIONAL TOTALS	TYPE "A" SIGNS 158.93 SF																				
SIGN SUMMARY SHEET							SHEET TOTALS	~~34.59~~ 35.34 SF	0.00 SF	0 EA	0 EA	0 EA	5 EA	0 EA	0 EA	6 EA		90 FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	162.7	0.0	16.0	1.0	1.0	29	0.0	0.0	35		525.0										

PROJECT NAME: STATEWIDE NORTHEAST
PROJECT NUMBER: STPG - SIGN (29)

FILE NAME: WOLCOTT EB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: D. CROSSLEY
WOLCOTT VT 15 EB 6

PLOT DATE: 8/18/2010
DRAWN BY: D. CROSSLEY
CHECKED BY: A. GAMBLE
SHEET 32 OF 138