DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.50	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	FOUNDATION	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
GLOVER NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.060	A	R2-1	24	30		SPEED LIMIT 35						1		X														
		A	R2-1	24	30			5.00								1		X									X		
NB	6.204	C	VR-017	24	30		LEGAL LOAD LIMIT 16,000 POUNDS						1		X											TALBOT LN TH-26			
		C	VR-017	24	30			5.00								1		X											E-141
NB	6.212	D	R1-1	30	30		STOP						1		X											TALBOT LN TH-26			
		D	R1-1	30	30			6.25								1		X								RE-INSTALL STREET SIGN ABOVE STOP SIGN.	X		
NB	6.267	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											SARGENT LN TH-25			
		A	N/A	24	8		SARGENT LANE				1				X											REMOVE STREET SIGN AND POST IN FRONT OF LLL. RETURN POST TO TOWN.			
		C	VR-017	24	30			5.00								1		X											E-141
NB	6.275	D	R1-1	30	30		STOP						1		X											SARGENT LN TH-25			
		D	R1-1	30	30			6.25				1				1		X								RELOCATE STREET SIGN ON STOP SIGN POST.	X		
NB	6.390	A	R2-1	24	30		SPEED LIMIT 40						1		X														
		A	R2-1	24	30			5.00								1		X									X		
							TOWN DIRECTIONAL TOTALS	TYPE "A" SIGNS 254.68 SF																					
SIGN SUMMARY SHEET							SHEET TOTALS	32.50 SF	0.00 SF	0 EA	1 EA	1 EA	6 EA	0 EA	0 EA	6 EA		90 FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	251.7	0.0	5.0	2.0	2.0	54	0.0	0.0	40		600.0											

PROJECT NAME: STATEWIDE NORTHEAST
PROJECT NUMBER: STPG SIGN (29)

FILE NAME: GLOVER NB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: D. CROSSLEY
GLOVER VT 16 NB 8

PLOT DATE: 8/18/2010
DRAWN BY: D. CROSSLEY
CHECKED BY: A. GAMBLE
SHEET 45 OF 138