DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	FOUNDATION	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
GLOVER SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	4.410	F	R2-1	24	30								1		X														
		F	R2-1	24	30			5.00								1		X									X		
SB	4.360	G	VR-017	24	30								1		X											PERRON HILL TH-37			
		G	VR-017	24	30			5.00								1		X											E-141
SB	4.350	H	R1-1	30	30								1		X											PERRON HILL TH-37			
		H	R1-1	30	30			6.25								1		X											
SB	4.100	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
SB	2.760	G	VR-017	24	30		LLL 16,000 LBS			+	x	x	x	~~x~~	x	1										DWINELL RD TH-44			
SB	2.700	F	W1-2L	30	30		LEFT CURVE						1		X														
SB	2.680	G	VR-017	24	30		L L L 24,000 LBS			1				X												SHADOW LAKE RD TH-2			
SB	2.666	H	R1-1	30	30		STOP			1				X												SHADOW LAKE RD TH-2			
SB	2.650	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
		F	W1-2L	30	30			6.25								1		X									X		
SB	2.621	F	W1-8 L	18	24	FY		1.50								1		X								INTALL 100' +/- NORTH OF MM 2.6	X		
SB	2.620	E	W1-8 R	18	24	FY		1.50								1		X								INTALL 100' +/- NORTH OF MM 2.6	X		
SIGN SUMMARY SHEET							SHEET TOTALS	25.50 SF	0.00 SF	3 EA	0 EA	0 EA	6 EA	0 EA	0 EA	6 EA		90 FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	225.8	0.0	5.0	2.0	2.0	46	0.0	0.0	44		660.0											

PROJECT NAME: **STATEWIDE NORTHEAST**
PROJECT NUMBER: **STPG SIGN (29)**

FILE NAME: **GLOVER SB**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **D. CROSSLEY**
GLOVER VT 16 SB 6

PLOT DATE: **8/18/2010**
DRAWN BY: **D. CROSSLEY**
CHECKED BY: **A. GAMBLE**
SHEET **51** OF **138**