DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.50	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	FOUNDATION	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
NEWBURY WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	4.459	E	W3-1	30	30			2.00					1		X														
		E	W3-1	30	30		STATE LAW SPEED LIMIT 50 UNLESS OTHERWISE POSTED 24X12 FY VBG-18P	6.25								1		X									X		
WB	4.430	F	R2-1	24	30			5.00								1		X								INSTALL OPPOSITE NEW SL 30	X		
		F	VR-208	24	24		USE R2-5P 24X8	3.00																				3	
WB	4.410	F	R2-1	24	30		SPEED LIMIT 50						1		X														
WB	4.195	F	W11-7	30	30		EQUESTRIAN SYMBOL						1		X														
WB	3.770	F	VW-133	30	30		HIDDEN DRIVE LEFT			1				X															
WB	3.640	G	VM-607	24	30		WILLIAM SCOTT MEMORIAL HIGHWAY						1		X														
WB	2.500	F	VD-062B	72	16		BUSINESS SIGN			1				X															
		F	VD-062B	72	16		BUSINESS SIGN			1																			
							RETAIN SIGNS UNLESS NOTED FROM 2.30 TO 1.58																						
WB	2.283	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											TH-29			
		G	VR-017	24	30			5.00								1		X											E-141
WB	2.281	H	R1-1	30	30		STOP						1		X											TH-29			
		H	R1-1	30	30			6.25								1		X									X		
SIGN SUMMARY SHEET							SHEET TOTALS	27.50 ~~26.50~~ SF	0.00 SF	3 EA	0 EA	0 EA	6 EA	0 EA	0 EA	4 EA		60 FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	216.0	0.0	6.0	2.0	2.0	57	0.0	0.0	29		435.0											

PROJECT NAME: STATEWIDE NORTHEAST
PROJECT NUMBER: STPG SIGN (29)

FILE NAME: NEWBURY WB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: D. CROSSLEY
NEWBURY US 302 WB 6

PLOT DATE: 8/18/2010
DRAWN BY: D. CROSSLEY
CHECKED BY: A. GAMBLE
SHEET 73 OF 138