DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.80	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
NEWBURY WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	M1-4	30	24		US 302						1																
		F	N/A	12	18		CROSS VERMONT TRAIL				1	1				1		X											
WB	0.060	F	R2-1	24	30		SPEED LIMIT 50						1		X														
WB	0.170	F	M3-4	24	12		WEST						1		X														
		F	M1-4	30	24		US 302						1																
WB	0.145	F	R2-1	24	30		SPEED LIMIT 50						1		X														
WB	0.000	G	VD-025	60	7.5		CALEDONIA CO/ORANGE CO						1		X														
		G	VD-024	60	7.5		RYEGATE/NEWBURY						1																
							TOWN DIRECTIONAL TOTALS	TYPE "A" SIGNS 26.95 SF																					
							SHEET TOTALS	0.00 SF	0.00 SF	0 EA	- EA	1 EA	7 EA	0 EA	0 EA	1 EA		15 FT											
							TOWN DIRECTIONAL TOTALS	26.95 216.0	0.0	6.0	2.0	2.0	57	0.0	0.0	29		435.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE NORTHEAST
PROJECT NUMBER: STPG SIGN (29)

FILE NAME: NEWBURY WB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: D. CROSSLEY
NEWBURY_US 302 WB_8

PLOT DATE: 8/18/2010
DRAWN BY: D. CROSSLEY
CHECKED BY: A. GAMBLE
SHEET 75 OF 138